MINISTRY OF EDUCATION AND SCIENCE OF THE REPUBLIC OF KAZAKHSTAN

Kazakh National Research Technical University named after K.I. Satpayev Institute of Architecture, Construction and Energy named after T. Basenov Department of «Construction and Building Materials»

1934

Kargar Babur

On the theme of "Multi-storey hostel in Taraz"

To the diploma project **EXPLANATORY NOTE**

Specialty 5B072500 – Civil Engineering

MINISTRY OF EDUCATION AND SCIENCE OF THE REPUBLIC OF KAZAKHSTAN

Kazakh National Research Technical University named after K.I. Satpayev Institute of Architecture, Construction and Energy named after T. Basenov Department of «Construction and Building Materials»

ALLOWED TO PROTECT

1934

Head of Department

K.Akmalayuli « <u>25</u> » <u>05</u> 2020 y.

EXPLANATORY NOTE

To the diploma project

On the theme of "Multi-storey hostel in Taraz"

Specialty 5B072500 – Civil Engineering

Prepared by

B.Kargar

Supervisor

N.V. Kozyukova

« 25 » 05_2020 y.

MINISTRY OF EDUCATION AND SCIENCE OF THE REPUBLIC OF KAZAKHSTAN

Kazakh National Research Technical University named after K.I. Satpayev Institute of Architecture, Construction and Energy named after T. Basenov Department of «Construction and Building Materials»

APPROVED

Head of Department

K.Akmalayuli

27

01

2020 y.

ASSIGNMENT Complete a diploma project

Student __ Kargar Babur __

Topic "Multi-storey hostel in Taraz"

№ 1222 b - endorsed by the request.

Approved by the Order of the Rector of the University No. 762-b of January 27, 2020.

The deadline for completion is May 18, 2020.

Beginning entries of the certificate venture: construction locale – Petropavlovsk. Rundown of issues to be considered in the recognition venture:

Architectural and development division: qualities of the development region; threedimensional arranging choices; structural and plan arrangements; external divider warm designing bookkeeping; building hardware of the structure;

Computational and valuable segment: count of burdens and making of the computation conspire, figuring of the board and its estimation of fortified solid components dependent on the outcomes and their motivation Technology and association of development creation and work security: land assurance of the volume of underground and surface works; assurance of the quantity of solid trucks; surface strengthened cement of the structure development of innovative guide of structures establishment; object plan of development end-all strategy; Schedule. 4. Division of Construction Economics: neighborhood and article planning of assessments, List of drawing materials (compulsory drawings must be indicated):

Facade of the structure, segments, joints, determinations, plans - 4 sheets;

Drawing, detail of the section - 2 sheets; Calendar arrangement of development creation, general development plan, 2 Sheets 11 slides of the presentation of work are provided.

Recommended basic literature: SP RK 2.04-01-2017 Construction Climatology, SN RK 2.04-04-2013 Construction Heat Engineering, SN RK 2.03-30-2017 Construction in Seismic Zones.

SCHEDULE preparation of thesis (project)

| No | Sections | 33% | 66% | 100% | Примечание |
|----|--------------------|--------------|--------------|---------------|------------|
| 1 | Predesign analysis | | | | |
| | Architectural and | 18.02.2019г | | | |
| | construction | 01.03.2019г. | | | |
| 2 | Settlement | | 18.03.2019г | | |
| | constructive | | 29.03.2019г. | | |
| 3 | Technology and | | | | |
| | organization of | | | 03.04.2020г | |
| | construction | 1 9 3 | 4 | 19.04.2020г. | |
| | production and | | - | | |
| | labor protection | | | | |
| | Economic | | | | |
| 4 | Anti-plagiarism, | | 18.05.2020y. | -22.05.2020y. | |
| | norm control, pre- | | | | |
| | defense | | | | |
| 5 | Defence | | 01.06.2020- | 05.06.2020y. | |

Signatures consultants and the normative controller for the completed diploma work (project) with an indication of the sections of work (project) related to them

| (project) with an indication of the sections of work (project) related to them | | | | | | | | |
|--|-----------------------------|------------|-----------|--|--|--|--|--|
| Name of sections | Consultants, I.O.F. | date of | Signature | | | | | |
| | (academic degree, rank) | signing | | | | | | |
| Architectural | N.V. Kozyukova, | 25.05.2020 | f f | | | | | |
| building | master of technical science | 25.05.2020 | fam J. | | | | | |
| Settlement and | Zh.T. Nashiraliev,candidate | 25.05.2020 | 1// | | | | | |
| constructive | of technical science | 23.03.2020 | Macy | | | | | |
| Technology and | I.Z. Kashkinbaev, doctor of | | | | | | | |
| organization of | technical science | 25.05.2020 | Weing | | | | | |
| construction | | 23.03.2020 | 1 | | | | | |
| production | | | | | | | | |
| Economic part | N.V. Kozyukova, | 25.05.2020 | 10 | | | | | |
| | master of technical science | 23.03.2020 | Jam J- | | | | | |
| Norm controller | N.V. Kozyukova, | 25.05.2020 | 80 | | | | | |
| | master of technical science | | fam J- | | | | | |

Supervisor The student accepted The task Date N.V. Kozyukova

«_25 » 05 _202

АНДАТПА

Дипломдық жобада Тараз қаласындағы көп қабатты жатақхана жобаланған.

Аймақтың бас жоспары бойынша техникалық көрсеткіштері:

- 1. Аймақ ауданы 7500 м^2 ;
- 2.Құрылыс аймағы -900 м^2 .

Диплом жобада сәулет – құрылыс, есептік-конструкциялық және өндірістік бөлімдер бойынша инженерлік шешімдер қабылданды. Жобаның толық ТЭК – і анықталып, қауіпсіздігі және еңбекті қорғау бөлімдері бойынша шешімдер қабылданған.

АННОТАЦИЯ

В дипломном проекте спроектирована многоэтажное общежитие в городе Тараз.

Технические показатели участка по генплану:

- 1. Общая площадь участка 7500 м²;
- 2. Строительный участок -900 м^2 .

В данном проекте в архитектурно-строительных, расчетно-конструкционных и производственных частях приняты инженерные решения. Выявлены общие технико-экономические показатели проекта, а также приняты решения о защите окружающей среды и безопасности жизнедеятельности.

ANNOTATION

In the diploma project a multi-story dormitory located in the city of Taraz. Technical parameters of the plot according to the general plan:

- 1. Building square -7500 m^2 ;
- 2. Building volume -900 M^2 .

In this project in architecture and construction, settlement construction and manufacturing parts made engineering decisions. The general technical and economic parameters of the project, as well as decisions on environmental protection and safety.

CONTENT

| Introduction | 7 |
|---|----|
| 1.2 Basic data on the construction site | 8 |
| 1.3 Architectural and planning decision | 9 |
| 2 Design | 10 |
| 2.1 Thermo technical calculation | 11 |
| 2.2 Structural part | 12 |
| 2.3 Calculation of the building in the software package LIRA-SAPR | 13 |
| 2.4 The calculation of the plate | 14 |
| 3 Technological part | 18 |
| 3.1 Characterization of soil development conditions | 19 |
| 3.2 Determination of the volume of earthwork | 20 |
| 3.3 List of Excavation volumes | 22 |
| 3.4 The selection of a set of machines for earthworks | 23 |
| 3.5 Statement of scope of work on the construction of foundations | 24 |
| 3.6 The aboveground part. Scoping | 27 |
| 3.7 Schedule 4 Health and safety | 30 |
| 3.8 Determination of variable operating capacity of the crane | 31 |
| 3.9 Determining the coast of a machine watch | 32 |
| 3.10 Design of the general construction plan | 33 |
| 3.11 Safety events | 33 |
| 3.11.1 Fire safety | 34 |
| 5 Economic part | 34 |
| Conculation | 35 |
| List of referience | 36 |

INTRODUCTION

First of all, architecture in our time should provide a safe living environment for the existence and activity of people in favorable conditions. The level of social and cultural development, scientific and technical achievements has a huge impact. In turn, all this potential is reflected in buildings, complexes of structures and buildings that have internal space and organize the external: squares, streets, cities.

Architecture is inextricably linked with the development of construction equipment. A log hut, a brick house, a metro station dominated by metal, marble, concrete, and an openwork metal bridge look completely different even at first glance. This means that a lot depends on the building materials that the architect uses. No less affect the architecture, the appearance of buildings and structures and building structures used in a particular era.

A multi-storey hostel provides the opportunity for a comfortable and active student stay and has a positive effect on learning. It is designed in such a way that it has the maximum usable area. This can be replaced by the number of rooms and the number of students. Our hostel is located in the city of Taraz. As we know, there are a lot of universities and colleges in the city.

Directly, when it comes to multi-story buildings, the issue of choosing structural forms that should be rationally chosen is raised, reducing the cost of concrete and metal, ensuring quick installation and reducing the complexity of manufacturing. This is achieved by comparing design options in which not only the structural scheme is analyzed and selected, but individual nodes and parts of the building are selected.

The chosen structural and planning solution of the building should provide stability, strength and spatial immutability of buildings and structures, as well as their individual elements during installation, transportation and operation.

Also, the reduction of construction costs is carried out by the correct choice of materials, both construction and finishing, reducing the weight of the structure, using modernized construction methods. The main reserve in the economic plan of urban development is to increase the level of land use efficiency.

1. Architectural part

Basic data on the construction site

The diploma project "Multi-story hostel" is located in the city of Taraz.

Taraz has the following climatic characteristics:

The region belongs IIIv climatic region with a sharply continental climate.

The average maximum temperature of the hottest month: 32,9°C

Absolute maximum temperature: 44,5°C

Absolute minimum temperature: -23°C

Average annual temperature: 12,8°C Naib. cold days security 0,98=-23°C, 0,92 = -23°C Naib. cold five-day security 0,98=-20°C, 0,92 = -26°C By the weight of the snow cover - II district (normal. Snow load 0.7 kPa) High-speed wind pressure - 38 kg / m2 building liability class - II Seismicity. The construction site is seismic hazard; magnitude is 8 points. Humidity Zone – Dry

Table 1 - Air temperature [10]

| Weather | Month | 1S | | | | | | | | | | | In |
|-------------|----------|---------|---------------|----------|----------|----------|----------|------|------|---------|-------|------|----------|
| station | | | | | | | | | | | | | a |
| | | | | | | | | | | | | | ye |
| | | | | | | 1 12 | | | | 10 | 1 4 4 | | ar |
| 3.6 .1.1 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | |
| Monthly and | d averag | ge annu | al air | tempe | rature, | ·C | | | | | | | |
| Taraz | - | - A | | | | | | | | | | - | |
| | 4,8 | 3,2 | 3, | 8,8 | 2 | 16, 7 | 4 | 17,3 | 12,9 | 6,7 | 1,8 | 0,4 | 8 |
| | Avera | ge max | imun | air te | mperat | ure, °C | C | | | | | | |
| | | | 21 | | | | | | | | | | |
| Taraz | | | | ٩ | | | | | | | | | |
| | -4 | -3.8 | 2. | 16, 5 | 8,7 | 12, 9 | 15, 7 | 19,8 | 34.4 | 12,9 | 6,2 | 0,4 | 14 ,6 |
| | Absol | ute max | imur | n air te | empera | ture, ° | C | | | | | | |
| Taraz | 17 | 19 | 26 | 33 | 35 | 39 | 43 | 40 | 36 | 31 | 25 | 19 | 43 |
| | Avera | ge mini | mum | air ter | nperat | ure, °C | | | 7 | | | | |
| Taraz | - ` | Ţ - | - | | | | | | | | - | | |
| | 11.1 | 9,5 | 2, | 5,6 | 10, | 15, | 17, | 16,3 | 11,0 | 4,6 | 3.3 | -5,8 | 3. 8 |
| | Absol | ute min | imun | air te | mperat | ture, °(| | | | I. | | | |
| | | | | | 1 | | | | | | | | |
| | | | | | | | | | | | | | |
| TD. | | | | | | 1 | 1 | I | | | | | |
| Taraz | 13 | 11 | 22 | - 11 | - 7 | 2 | 7 | 5 | 3 | - 11 | 20 | 12 | - 18 |
| | 13 | -11 | 22 | 11 | / | 2 | / | 3 | 3 | 11 | 20 | 12 | 10 |
| | 1 | | I | 1 | 1 | 1 | 1 | 1 | l | l | | L | |

Table 2 - Snow cover [10]

| Weather station | mo | nths | _ | | | | | | | Highes | st winter | values |
|-----------------|----------------------------------|------|----|----|----|----|---|---|---|--------|-----------|--------|
| | 9 | 10 | 11 | 12 | 1 | 2 | 3 | 4 | 5 | Avg. | Max. | Min. |
| e average mo | e average monthly snow depth, cm | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | 4 | 10 | 21 | 9 | | | 28 | 55 | 7 |
| | | | | 9 | 3 | 4 | ı | | | | | |

1.2 Architectural planning solution

The hostel being designed forms a courtyard space on the general plan, where there are playgrounds for adults, playgrounds, tennis courts, flower beds and gazebos.

The vertical facade is emphasized by vertical stained glass glazing along the bay windows, and horizontal by fiber-reinforced concrete decorative belts.

Horizontal communications on floors are provided through elevator halls and corridors, and vertical communications are provided by a staircase and an elevator with a carrying capacity of 630 kg (cabin speed -1.0 m / s) The collection of household waste is carried out in the garbage chambers of garbage chutes with their subsequent removal by special transport to the city landfill for recycling and disposal. Garbage chutes are designed from an asbestos-cement pipe with a diameter of 400 mm

The stairwell is connected to the elevator hall with a wide opening. This opening provides natural light to the elevator hall Elevator doors must be made of non-combustible materials. When developing a graduation project, the task was solved to ensure the maximum comfortable living conditions for students, while creating a memorable harmonious image.

1.3 Constructive solution

For the conditional mark of 0,000, the mark of the clean floor of the 1st floor of the hostel is taken. Building structures are designed for a seismicity of 9 points. The construction site is potentially unsinkable. Groundwater lies at a depth of more than 3.0 m The main building structures: foundations - monolithic reinforced concrete slab 800 mm thick from concrete class B25; the basis of the foundations are pebble soils with sand aggregate; external walls are monolithic reinforced concrete; monolithic reinforced concrete columns with a

section of 500x500 from concrete of class B25; monolithic reinforced concrete crossbars with a section of 500x500 (h) from concrete of class B25;

monolithic reinforced concrete floors 200 mm thick from concrete of class B25; - the roof is flat along the reinforced concrete floor of the staircase, monolithic reinforced concrete of class B25.

Ant seismic measures:

The supporting structure of the building - a monolithic reinforced concrete frame, combined with a monolithic overlap into a single spatial system - is a reliable structural scheme, calculated and designed for seismic effects with a force of 9 points. foundations are based on reliable non-sagging soils. Anticorrosion measure surfaces of reinforced concrete structures in contact with the ground are covered with hot bitumen for 2 times. When performing work, be guided by the instructions: SNiP 3.02.01-87 "Earthworks, foundations and foundations"; SNiP RK 5.03-37-2006 "Bearing and enclosing structures"; SNIP RK 1.03-05-2001 "Occupational health and safety in construction". The construction of a multi-story dormitory is envisaged in the nine-point zone of the city of Taraz in subzone II-A-1 according to the microseismic zoning map.

The structural design of the building was adopted in full accordance with the requirements of earthquake-resistant construction standards and the calculations made on the LiraSAPR program student version.

1.4 Thermo technical calculation of building envelopes

Initial data for calculating the outer brick wall of the building. The construction area of the complex is Taraz. Estimated winter outdoor temperature tn = -23 $^{\circ}$ C. Calc. internal air temperature tv = 18 $^{\circ}$ C




Figure 1.1 - The outer walls of the strata. 310 mm

Table 1.1 - Wall Layers

| № | Names | δ (M) | λ, (Bτ/м·°C) | S |
|---|--------------------------|-------|--------------|-------|
| 1 | GKL decorative element | 0,015 | 0,19 | 3,12 |
| 2 | Mineral wool | 0,04 | 0,07 | 4 |
| 3 | Reinforced concrete wall | 0,2 | 1,92 | 17,98 |
| 4 | Roofing layer | 0,002 | 0,17 | 3,53 |
| 5 | IAF | 0,005 | 0,35 | 21,53 |

The heat engineering calculation is performed according to the joint venture of the Republic of Kazakhstan 2.04-01-2017 "Construction Climatology" and SNiP RK 2.04-03-2002 "Construction Heat Engineering"

We determine the value of the degree days of the heating period:

$$\Gamma CO\Pi = (t_{B} - t_{OTITEP}) * Z_{OTITEP}$$
(1.1)

$$\Gamma \text{CO\Pi} = (t_{\text{B}} - t_{\text{cp.ot.}}) \cdot z = (18 + 0.7) \cdot 162 = 3029.4$$

где $t_{cp.or.}$ =-1,6°C- the average temperature of the heating season [3, p. 14]; z = 162 days - the duration of the heating period. For GSOP = 3029.4

 $R_0^{\text{тp}}$ =0,38 м²°C/Вт. 1[3,стр15-16,табл.4] The necessary thermal resistance of the fence to ensure comfortable conditions:

$$R_0^{mp} = \frac{(t_g - t_H)}{\alpha_g \cdot \Delta t_H}$$
 [3, tcr16, f-le 4] (1.2)

$$R_0^{mp} = \frac{1 \cdot (18 + 23)}{8.7 \cdot 4} = 1,05 \frac{M^2 \cdot {}^{\circ}C}{Bm}$$

Heat transfer resistance:

$$R_0 = \frac{1}{\alpha_s} + \frac{\delta_1}{\lambda_1} + \frac{\delta_2}{\lambda_2} + \frac{\delta_3}{\lambda_3} + \frac{\delta_4}{\lambda_4} + \frac{1}{\alpha_u}$$
 [15, f-le3, 5] (1.3)

where $\alpha_{s} = 8.7$ [3, tcr. 17, scad. 5]

 $\alpha_{H} = 23 [3, \text{ tcr. } 18, \text{ scad. } 7]$


$$R_0 = \frac{1}{8.7} + \frac{0.015}{0.19} + \frac{0.04}{0.07} + \frac{0.005}{0.35} + \frac{0.2}{1.92} + \frac{0.002}{0.17} + \frac{1}{23} = 1.07 \frac{M^2 \cdot {}^{\circ}C}{Bm}$$

To check the suitability of the wall, we check:

$$R_0^{mp} \le R_0 \tag{1.4}$$

$$R_0^{mp} = 1,05 \frac{M^2 \cdot {}^{\circ}C}{Bm} < R_0 = 1,07 \frac{M^2 \cdot {}^{\circ}C}{Bm}$$

The selected thicknesses of materials satisfy the requirements of thermal engineering calculation. Choose a wall with a thickness of 310 mm.



2 Structural part

2.1 Calculation of the building in the software package LIRA-SAPR

By calculating the building in the LIRA-SAPR software package, we obtain the data that are then used in the calculation of structures manually — the forces that occur in the elements. The building scheme was built directly in the LIRA program. Loads are set in accordance with the regulations. The loads from the floor, partitions, soil pressure are also set, the snow load is set in accordance with the snow area of construction. A seismic area is also taken into account. Initially, we set the design parameters in accordance with the Architectural part. In the case of large deformations, the cross section can be increased or a different type of structural element can be selected.

The collection of loads specified on the Lira CAD Total nodal loads on the main circuit: Load

```
1 PX = 0 PY = 0PZ = 9096.81 PUX = 2.79932e-014 PUY = -9.53196e-014
PUZ = 0

Load 2 PX = 0 PY = 0 PZ = 8167 PUX = 2.65517e-014 PUY = -1.06207e-
013 PUZ = 0

Load 3 PX = 0 PY = 0 PZ = 2624 PUX = 0 PUY = 0 PUZ = 0

Load 4 PX = 0 PY = 0 PZ = 1530.6 PUX = 1.77011e-014 PUY = -4.42528e-
014 PUZ = 0

Load 5 PX = 0 PY = 0 PZ = 2040.8 PUX = 4.42528e-014 PUY = -7.9655e-
014 PUZ = 0

Load 6 PX = 0 PY = 0 PZ = 612 PUX = 0 PUY = 0 PUZ = 0 The calculation results
```

in LIRA-CAD are given in Appendix A




Figure 2.1 - Design combinations of efforts




Figure 2.2 - Estimated combination of loads

This building model is designed in accordance with the design features of the designed building. The stiffness and overlap diaphragms were modeled by finite elements of a flat shell. The design model of the building is adopted in the form of a spatial multi-mass discrete system with masses concentrated in nodes. Each node has 6 degrees of freedom.




Figure 2.3 - The initial spatial model of the building

Various calculation files are created to meet the norms of SNiP and the design features of the designed building.

2.3 The calculation of the slab

For the calculation, a structural element was chosen - a plate at the mark of $\pm 3,000$ along the axis 3-4 / V-G.




Figure 2.4 - Moment (MX) in the floor slab at elev. +3.00




Figure 2.5 - Moment (Mu) in the slab at elev. +3.00




Figure 2.6 - Moment (Mz) in the floor slab at elev. +3.00




Figure 2.7 - Construction of the floor slab on the bottom




Figure 2.8 - Construction of the floor slab on the upper face Initial data:

Plate of cube cross section with bottom reinforcement with dimensions b = 1000 mm, h = 200 mm; ; Concrete has a normal class C25 / 30

$$(f_{ck} = 25 \text{ M}\Pi a, \gamma_c = 1.5, f_{cd} = 14.2 \text{ M}\Pi a, \alpha_{cc} = 0.85)$$
 (2.1)

Reinforcement class S500

$$(f_{vK} = 500 \text{ M}\Pi a, f_{vd} = 435 \text{ M}\Pi a$$
 , $E_s = 20*10^4 \text{ M}\Pi a$, $\alpha_{cc} = 0.85)$

According to the calculation on the Lira Sapr maximum torque is $= 21.7 \text{ kN} \cdot \text{m}$.

A) Determination of the cross-sectional area of the reinforcement Bending moment acting in section:

$$21.7 \text{ kN} * \text{m.} (= 0), d = \text{h-} = 200 - 20 = 180 \text{ mm}.$$

The required area of longitudinal reinforcement is determined according to:

$$k_{d} = \frac{d}{\sqrt{M_{ed}/b}}$$
 (2.2)

$$k_d = 3.0$$

$$k_{d} = 3.0$$
Determine according to table B.3 for normal concrete \leq C $25/30 \rightarrow = 2.4$

$$A_{s1} = k_{s1} * \frac{M_{eds}}{d} + \frac{N_{ed}}{\sigma_{s1d}} = 2.4 * 21.7/18 + 0/435 = 2.9 \text{ cm}^{2}$$

Accept: $50/12 (A_{s1} = 5,65 \text{ cm}^2)$

b) The selection of longitudinal reinforcement (see example 3) is carried out according to table B.1 of Appendix B to determine the bearing capacity of bent rectangular elements with a single reinforcement using dimensionless coefficients We determine the value of the coefficient

$$\alpha_{\text{eds}} = \frac{M_{\text{eds}}}{f_{\text{cd}} * b * d^2} \tag{2.4}$$

$$\alpha_{eds} = 0.047$$
 $\alpha_{eds} \le \alpha_{eds,lim} = 0.372$
 $0.047 < 0.372$

Compressed fittings are required by design. We put it constructively. 5Ø 10 ($A_{s2}=3.93 \text{ cm}^2$

C) Calculation of checking the width of the opening of cracks normal to the longitudinal axis of the element Working section height

$$d = h - ccov - dsw - \emptyset 12/2 = 200 - 20 - 12/2 = 174 \text{ MM}.$$

 $\rho = As1/bd = 565/1000 \cdot 174 = 0,0032 (0,32\%).$

Check the width of the crack opening by a simplified method, using the data in table. 8.3 for rectangular sections reinforced with reinforcement of class St500 with ρ ≤0.5% the shoulder of an internal force pair is determined:

$$z = 0.85d = 0.85 \cdot 174 = 147.9 \text{ MM}$$

Stresses in tensile reinforcement are determined by the formula;

$$\sigma_{\rm S} = {\rm Med/As1 \cdot z}$$
 (2.5)

$$\sigma_{\rm S} = 259.7 \; \text{H/mm2}$$

According to the table 8.4 dmax = 20 mm at σs = 259.7 MPa and wk, lim = 0.4 mm. The accepted diameter $\emptyset = 12 \text{ mm} \le \emptyset max = 20 \text{ mm}$, i.e. it is not necessary to check the crack opening width by calculation.

3 Technological part

3.1 Preparation of construction site areas

Preparatory work includes: cleaning of areas, areas, groundwater management, creation of a geodetic distribution base.

When clearing the areas, for the first time the lands to be developed will be planted with greenery, the areas will be cleared of weeds, unnecessary structures will be demolished, and the soil will be covered with grains. The lawn, which cannot be uprooted or moved, is surrounded by a common fence.

Destroys non-collapsible wood, stone and concrete structures due to falls. Wood can be burned on the spot in coordination with the fire and sanitary control of the building. Assembles monolithic reinforced concrete and metal structures.

The grain layer of the soils to be removed from the construction areas will be cut for re-use and relocated to a special disposal site.

The construction area must be fenced or marked with identical signs and inscriptions.

When designing a construction grid, the divider should be as flexible as possible to create axes.

The creation of a geodetic dividing base is the action of the customer. Ten days before the start of construction, the lessee must provide technical documentation on a geodetic basis.

3.2 Earthworks

The excavator driver should try to make the most of the structural capabilities of the machine and the power of the engine when creating the soil. The duration of work with the excavator is reduced due to turning, lowering and lifting joints. When making a pit, it is recommended to place the carriers on the side.

This reduces the working time and creates favorable conditions for the operation of the mechanisms.

Control over the correctness of the work is carried out in accordance with the requirements of SNiP 3-5-76 "Control over the correctness of earthworks" and the correctness of the work is checked monthly by the manufacturer and foreman.

Acceptance of completed earthworks in a separate area is carried out by the foreman of the excavator team on the size and size of the building, produced by a craftsman or a manufacturer. Object or building acceptance, subject to verification: compliance of geodetic dimensions in the section, as well as in the plan project.

3.3 Installation of crossbars

When preparing the crossbars for installation, they clean and smooth the inserted parts, apply the protrusions of the reinforcing springs and strengthen them with springs. No special crossbars are required before installation.

It does the job well. Welding of crossbars with poles allows them to be installed quickly when they are installed. Crossbars with poles 29 During welding and installation, installers and welders are located on the ground of group conductors.

3.4 Installation of wall panels

Inventory molding of large shields is used for wall construction. Assembles in the form of panels across the entire wall width. First of all, install the inner panel. Its position is fixed by means of a sloping support and tension. After removing the project condition with the help of a jack jack, install the outer molding panel. The design dimensions of the wall for the city of Almaty connect the upper strips of the inner and outer panels with the help of tensioners.

The shields are delivered by crane. When building a slightly elongated wall, use several panels of the formwork. Normal installation begins with corner shields that serve as beacons. They are installed in strict accordance with the separation axes and fastened with temporary supports and diagonal supports. Install shields in vertical planes with the help of screw jacks. The lighthouse shields are installed one after the other along the length of the wall. The shields are fastened to each other with bolts. The rigid edges of the frame are designed for mounting anchors and crowns with a pitch of 1200 mm. Anchors and crowns are made of periodic or flat profile d16mm rods.

The stability of the panel form is ensured by inventory ramps and ropes. During the installation of the crowns, the adjusting screws of the jacks push the inventory inclined supports up to 20-30 mm from the vertical to the horizontal.

After installing the anchor, remove the normal adjuster relative to the vertical axis with the help of jack-sloping supports.

After installation and removal of all panels, on one side of the formwork on the inventory brackets are installed working linings that provide support for the railings. When building a wall with a height of more than 3.69 m, the formwork is installed in several tiers. Depending on the degree of concreting of the structure under construction, the 2nd and tier forms are supported on the bottom, or fastened to the wall with special anchors, or supported on special brackets or beams.

3.4 Installation of ceilings and roof slabs

The sequence of operations on the formation of the ceiling and the organization of work in Almaty depends on the structural scheme of the building or structure and

the type of ceiling. Flat ceilings are concreted in a form that rests on load-bearing walls and beams, the load-bearing elements of which are movable crossbars. Without intermediate supports 30 Distances of up to 6 m can be covered using sliding supports. At 12 m intervals, intermediate supports - steel or wooden beams - should be installed on telescopic supports.

Normal assembly begins with the removal of marks on the wall or beam support slots. If necessary, the molds are poured with cement-sand mortar or leveled with hard pavements. Then install the movable crossbars with the calculated step. When using shield forming, movable crossbars can be installed in 300, 400, 450, 600, 900 steps. A prerequisite for the production of work is the support of the shields on at least three crossbars. These conditions are required by safety regulations. When using a board of wood, plywood, or chipboard as a board, the pitch of the crossbars may be different and is calculated.

3.6 Installation of marching areas

Before installing the IIS-04 frame ladder, it is necessary to install a fencing panel on the ceiling of the crossbar, which must be closed in accordance with the design.

The prefabricated stair treads are placed on the design site and installed in a cement-sand layer with a thickness of 1 cm with the help of a fork joint connected with the semi-sections. In addition, first the lower half of the area is shot, and then the upper half. Then he starts welding the parts to be built in the area. During the installation of the stair treads of the semi-areas of the upper floors, the parts of the prefabricated iron enclosure are pre-welded to the latter, with the help of which the routes meet the crossbars and the intermediate roofing panel. Then iron fences are welded to the marches. Determination of technical parameters of self-propelled crane

1) Determination of load capacity:

$$Q=Q1+Q2$$
 (3.1)

where Q1 – mass (weight) is the weight of the heaviest mounting element.

Q 2 – mass of sling equipment.

Determine the output of the arrow

$$l_{cmp}^{mp} = \frac{(e+c+d)(H_{cmp}^{mp} - h_w)}{h_c + h_n} + a$$
 (3.2)

$$h_w=1.5$$
 a=1.5
$$l_{cmp}^{mp} = \frac{(0.5+1+1.5)(11.25-1.5)}{1.6} + 1.5 = 19.78$$

Determine the length of the arrow

$$L_{cmp}^{mp} = \sqrt{(l_{cmp}^{mp} - 2)^2 + (H_{cmp}^{mp} - h_w)^2}$$
 (3.3)

$$L_{cmp}^{mp}$$
 (19, 78-1,5)²+(11,25-1,5)²=20,8

Based on the following parameters, we choose two self-propelled cranes LPG-40A



Figure 3.1 - Scheme for determining the required parameters of the crane h0 -is the height from the parking level to the longest enclosure

Hz- is the height reserve

hc- is the height of the strap

he- is the height of the element in the mounting position

hsh- is the distance from the parking level of the crane to the axis of rotation of the arrow

hp- is the height of the pulley

a -is the distance from the axis of rotation of the crane to the axis of rotation of the narrow

 l_{cmp}^{mp} - Arrow release

 H_{cmp}^{mp} -Arrow lifting height p

 L_{cmp}^{mp} -Arrow length

3.8 Determination of variable operating capacity of the crane

Table 3.1-Determination of variable operational capacity of the crane

| Data names and calculation formulas | | Brands of truck cranes LPG-40A |
|-------------------------------------|---|--------------------------------|
| 2 | 3 | 4 |

| The lifting height of the hook, H_{cmp}^{mp} | 11.25 | 11,25 |
|---|-------|-------|
| The average angle of rotation of the arrow, a | 120 | 105 |
| Average load displacement interval in arrow output change, S2 | 6 | 6 |
| Approximate crane travel distance, S1 | 4,8 | 55,4 |
| Crane lowering and lifting hook speed, v1 | 14,2 | 17,6 |
| Determination of crane speed, n | 0.6 | 0,6 |
| Crane speed, v2 | 17,7 | 17,9 |
| Travel speed The speed of the truck with the change of the output of the arrow, v3 | 24,6 | 28,6 |
| Additional time for braking and activation of crane components, tdop Crane cycle machine time | 3 | 3 |
| Time of manual work, Trust = Toast + Trust | 5,89 | 5,49 |
| Full cycle time, Тц = Тмаш + Труч | 24,09 | 30,2 |
| Variable capacity of the crane,: | 73,30 | 67,41 |

3.9 Determine the cost of a machine watch

Table 3.2- Determine the cost of the machine clock

| Data names and calculation formula | cranes LPG-40A | Brands of truck KC8167 |
|-------------------------------------|----------------|---------------------------|
| 2 | 3 | 4 |
| Data names and calculation formulas | 62,3 | 123,5 |
| Depreciation, A | 10,8 | 10,8 |

| Quantitative number of working hours per crane per year, Dm | 420 | 420 |
|---|------|-------|
| Installation and dismantling cost of the crane, MD | 1650 | 1950 |
| , | | |
| The cost of transporting | 79,2 | 123,5 |
| the crane from object to object, p | 1934 | |
| Number of crane working hours at a given facility, Do. | 1104 | 1104 |
| Maintenance and repair costs, R | 3,43 | 3,79 |
| Costs for replacement auxiliary devices and load-bearing units, B | 0,25 | 0,3 |
| Energy costs, E. | 1,09 | 0,89 |
| Costs of combustible materials, C | 0,22 | 0,18 |

Table 3.3-Determining the scope of work in units of volume

| Data names and calculation | Brands of truck crane | | |
|--|-----------------------|--------|--|
| formulas | LPG-40A | KC8167 | |
| 2 | 3 | 4 | |
| Installation of labor volumes of construction structures, T mash | 5,89 | 5,49 | |
| | 18,2 | 24,8 | |

| Labor costs of manual labor, Truch | | | |
|---|---------|---------|--|
| Labor costs for equipment for maintenance and repair of crane tracks, Tput | - | - | |
| Labor costs for crane maintenance and replacement, Tex | 4,6 | 7,2 | |
| Labor costs for delivery of the crane | | | |
| to the object, T per 9 3 4 | 29 | 43 | |
| Scope of work, V | 1284,65 | 1284,67 | |
| Labor costs of construction structures measurement of work volume in units, T | 0,82 | 0,91 | |

Technical and economic performance of self-propelled cranes.

Table 3.4 - Technical and economic performance of self-propelled cranes.

| Variants assembly cranes | | Variable cran displacement capacity | The cost of a car watch | The volume of work in units of work |
|--------------------------------|---|-------------------------------------|-------------------------|-------------------------------------|
| 1 | | 2 | 3 | 4 |
| LPG-40A | 1 | 73,30 | 1251 | 0,62 |
| KC8167 | | 67,40 | 2405 | 0,91 |

Selecting the TEC of cranes, we choose the crane LPG-40A, which shows very good performance.

3.10 Design of the general construction plan

Table 3.5 - Calculation table of open storage areas.

| materia | als | unit | Ge ner al | Dail y | The amo unt per day | The amo unt is man ual. co | Coef ficie nt of incid ence | Stoc k calc ulati on | of the fund | acce ss to grai n. | |
|--|------|------|-----------------|-----------|---------------------|----------------------------|---|----------------------------------|-------------------|-----------------------------|------------|
| 2 | | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 |
| Founda ns | atio | pice | 35 | 31,8 1 | ² 3 | 1,3 | 1,1 | 90,9 7 | 1,2 | 0,6 | 126, 34 |
| Pillars | | pice | 82 | 16,7 3 | 2 | 1,3 | 1,1 | 47,8 4 | 1,8 | 0,6 | 44,2 |
| Crossb | ars | pice | 55 | 13,4 1 | 2 | 1,3 | 1,1 | 38,3 5 | 0,45 | 0,6 | 142, 04 |
| Stairca and marche | | pice | 12 | 2,79 | 2 | 1,3 | 1,1 | 797, 94 | 0,6 | 0,6 | 221, |
| Slab joints interse openin for column | gs | pice | 11 1 | 34,6 | 2 | 1,3 | 1,1 | 99,1 | 0,45 | 0,6 | 367, 35 |
| Wall panels | | pice | 39 | 15,6 | 2 | 1,3 | 1,1 | 44,6 1 | 1,6 | 0,6 | 40,4 7 |
| Partition walls | on | pice | 34 | 26,1 5 | 2 | 1,3 | 1,1 | 74,7 8 | 2 | 0,6 | 62,3 4 |
| Stained glass window | | pice | 9 | 7,5 | 2 | 1,3 | 1,1 | 214, | 0,3 | 0,6 | 119 1,6 |
| Bricks | | pice | 1,0 2 | 0,51 | 2 | 1,3 | 1,1 | 1,45 | 0,7 | 0,6 | 3,45 |
| Gravel | | pice | | | 2 | 1,3 | 1,1 | | 1,5 | 0,6 | |
| Undergund | gro | pice | 72 | 40 | 2 | 1,3 | 1,1 | 114, 4 | 1,2 | 0,6 | 158, 8 |

| panels | | | | | |
|--------|--|--|--|--|--|
| | | | | | |

Table 3.6 - Table for calculating the area of temporary buildings

| Table 3 | .0 - | Table | | il Culai. | ing inc | | Cmp | orary buildi | ngs |
|--------------------|----------|----------|------|-----------|---------|-------------|-----|---------------|-------------------|
| | | | Nu | Ауда | aн, | Meas | | | |
| Mamaa | | The | m | м2 | | ure | | The | |
| Names | | num | be | | | the | | project | T 0 |
| buildings | S | ber | r | For | | tempe | | typical | Type of |
| and | | of | of | 1 | Gen | rature | | number | building |
| structure | es | | | | | | | | |
| | | tuts | jo | wee | eral | in the | | of | |
| | | | bs] | k | 3 | pair. | | | |
| 2 | | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 |
| Place leadershi | of ip | 100 % | 1 | 4 | 4 | 6x 2 | 2 | 420-04 | Containeriz ed |
| Contact | | 100 % | 4 | 7 | 28 | 6 x 6,9 | 2 | 420-04- 11 | Containeriz ed |
| Walking area | | | 46 | 18 | 18 | 6x 3 | 2 | 420-04- 30 | Containeriz ed |
| Clothes storage | | 100 % | 46 | 0,7 | 32,2 | 2,7 x 18 | 2 | 420-01-8 | Containeriz ed |
| Bathroon | m | 50% | 23 | 0,5 | 11,5 | 2,7x 18 | 1 | 420-01-8 | Containeriz ed |
| Take shower | a | 50% | 2 | 0,5 | 1,08 | 2,7 x 18 | 1 | 420-01-8 | Containeriz ed |
| Drying room | | 40% | 18 | 0,2 | 3,6 | 4x 3 | 1 | ГПД-9 | Containeriz ed |
| Heating place | | 50% | 23 | 0,1 | 2,3 | 2,7 x | 1 | 420-04-9 | Containeriz ed |
| Place eat | to | 50% | 23 | 1 | 23 | 6,9 x 18 | 1 | 420-04- 34 | Containeriz ed |

| Toilet | 100 % | 46 | 0,1 | 4,6 | 2,7 x 6 | 1 | 420-04- 23 | Containeriz ed |
|--------------------------|-------|----|-----|------|---------|---|---------------|-------------------|
| Women's personal hygiene | 30% | 13 | 0,1 | 2,34 | 6x 2 | 1 | 420-04 | Containeriz ed |

Table 3.7-Calculation table of buildings and structures intended for production

| Names of buildings and structures | The size of the building | Керекті аудан | . Үймереттің түрі |
|-----------------------------------|--------------------------|------------------|-------------------|
| Structures | in the plan | аудан | |
| 2 | 3 | 4 | 5 |
| Dense-forge-workshop | 9,97x7,23 | 57,6 | Scattered |
| Electrical installation workshop | 4,1x2,2 | 8 | Scattered |
| Sanitary and technical workshop | 6,6x9 | 8 | Scattered |
| Equipment workshop | 6,6x9 | 41,4 | Scattered |
| Closed storage | 6x6 | 34 | Scattered |
| Malari station | 4,5x2,5 | 22,4 | Scattered |
| Plastering station | 4,5x2,5 | 11,25 | Scattered |
| Reinforcement workshop. | 4,1x2,2 | 8 | Scattered |

Table 3.8 - Calculation of water demand

| Usernames | Mea sure. unit | Everythi ng | Allocat ed water consu mption | The amount Of water used is z coefficiet | Number of hours of water use | Water consu mptio n |
|---|----------------------|----------------|---|--|------------------------------------|-----------------------|
| 2 | 3 | 4 | 5 | 6 | 7 | 8 |
| I. Production needs Plastering Works Painting Preparation of | M2 M2 M3 | 205 238 66 | 7 0,5 200 | 1,5 1,5 1,5 | 16 16 16 | 0,03 0,004 0,35 |

| mortar for wall cladding | | | | | | |
|--|--------------|-------|-------|-----|---------|-------|
| II. Domestic- drinking water Consumption of water for domestic | адам адам | 46 23 | 15 30 | 3 1 | 16 0,75 | 0,017 |
| needs | | | | | | |
| Consumption of water for bathing | | 193 | 3 4 | | | |
| III. Fire safety accessories | га | | | | = | 10 |

Water consumption for production needs is determined by the following formula:

Wend = Bpart1
$$\cdot$$
 V \cdot K1/t1 \cdot 36

Part 1 is the allocated water consumption

V-size

K1- excess water consumption factor t1 is the number of hours of water consumption Household water consumption is given by the following formula determined by:

$$Vturm = B part2 \cdot N total \cdot K2/t2 \cdot 3600$$

- 1) Publication of construction should begin only with the permission of the manufacturer.
- 2) Before cutting it is necessary to obtain the conclusion of the construction laboratory on the actual strength of concrete.
- 3) Vibrating handles must have testers, and power cords must have reliable rubber insulation.
 - 4) Regular medical examination of concrete workers working with vibrators.
- 5) Workers welding fittings must have personal protective equipment. 6) Each employee undergoes an introductory instruction at the workplace before the start of work.
- 7) Measures shall be taken to prevent spontaneous opening of bunker fasteners when feeding concrete mix in bunkers.
- 8) Inspects all forklifts, mechanisms and devices used on the construction site in accordance with the rules of state technical supervision before use.
 - 9) Works on crane supports during installation of fittings.

- 10) It is strictly forbidden for people to be in the work area during the operation of the crane.
- 11) It is prohibited to unpack or leave the suspended cargo unattended, as well as to carry out installation in winds of more than 6 points.
- 12) It is strictly forbidden to operate the tower crane directly under the wires of any high-voltage power lines during operation.
- 13) It is allowed to connect welding transformers and lighting devices only to the electrician on duty.
- 14) Welding transformers are connected to the mains only with the help of closed circuit breakers.
 - 15) Welded products are welded to the bodies of welding transformers.
- 16) Welding transformers are connected to the network only with the help of circuit breakers.
- 17) Welding transformers installed in the open field are covered with a canopy or tarpaulin from atmospheric precipitation, as well as protected from mechanical damage.
- 18) Electric welding in the open air during thunderstorms and rain is prohibited.
- 19) The voltage at the terminals of welding transformers should not exceed 70 V when igniting the arc.
- 20) Repair, adjustment, adjustment and cleaning of the transformer under voltage are prohibited.
- 21) It is allowed to hold another welding transformer only when it is disconnected from the power supply.
 - 22) Workers may be lowered into the pit or trench only by stairs.
- 23) If cracks appear in the pits or trenches, it is necessary to fix the walls or reduce the slope before starting work.

3.11 Safety equipment and labor protection

3.11.1 Safety events

Production work must be carried out with the obligatory observance of the rules of technical safety, fire safety, labor protection in accordance with the requirements of SNiP RK 1.03-05-2001 "Labor protection and safety regulations and equipment safety" documents in construction. Responsibility for the implementation of safety measures, labor protection, fire and environmental safety is assigned to the managers of the work, assigned by the order. Security Tools (special clothing, shoes, etc.), sanitary and household security along the individual protection (fencing, lighting, ventilation, protective and protective devices and equipment, etc.), sanitary and household premises and facilities in accordance with applicable norms and the nature of the work performed. Workers must create the necessary conditions for work, nutrition and rest.

Responsibility for the performance of safety measures, labor protection, fire and environmental safety is assigned to the managers of the work, assigned by the order.

sanitary-safe premises and facilities in accordance with applicable norms and the nature of the work performed. Workers must create the necessary conditions for work, nutrition and rest Duration of the preparation of Their continuity. The need for labor resources is established by taking into account the safety of work and the timing of activities, ensuring safe production of work that any of the operations performed was not a source of production hazards for simultaneously performed or subsequent work.

In the development of methods and the sequence of work, it is necessary to take into account the hazardous areas that arise in the process of work. In case of necessity of performance of works in dangerous zones, it is necessary to provide measures for protection of employees. All persons located on the construction site are obliged to wear protective helmets, workers and engineering and technical workers without protective helmets and other necessary means of individual protection. Employees of individual means of protection must correspond to their floor, growth and size, character and conditions of the work performed and to ensure the reduction of the impact of harmful and dangerous factors of production.

The employer must organize the appropriate care for the means of individual protection and their storage, timely perform dry cleaning, washing, repair, decontamination and dusting of special clothing, special footwear and other means of individual protection., as well as dryers and chambers for providing special clothing and footwear.

Drying and dusting of special clothes are carried out after each shift, washing or dry cleaning - according to the need, but not less than twice a month.

The construction site is enclosed by a temporary panel-and-fence enclosure with a height of 2.0 m in accordance with GOST 23407-78. The width of the passages for one-way traffic should be no less than 3.5 m, for two-way traffic - not less than 6.0 m, and for a load-lifting crane - not less than 5.0 m.

For the proper organization of traffic on the territory of construction sites are installed indicators of travel, road signs with the designation of the maximum speed, parking places in accordance with GOST 10807-78. The pits and trenches along the upper edge of the trench should be fenced off. For the passage through the dug trenches and trenches are installed pedestrian bridges with a width of not less than 0.8m with double railings with a height of 1.0m. Artificial lighting of workplaces, passages and passages is carried out in accordance with the "Standards of electrical lighting of construction and installation work." During the dark hours of the day, the construction site is illuminated by floodlights PKN-1000-2, installed on the reconstructed building and temporary supports. Safety and technical inspection activities are carried out by the safety engineer in compliance with the production project. During the production of work to fulfill the requirements of PPB 01-03 "Fire safety rules", on the safety of work with power tools, equipment, small machinery construction equipment. and

Submit the PPR to all participants of the production process at the time of registration.

3.11.2 Fire safety

For heating inventory of temporary buildings, as a rule, steam or water heaters should be used, as well as electric heaters of factory production. Dry clothes and shoes should be produced specifically adapted for these purposes in the premises with central water heating or with the use of water heaters. The device for drying in tambours and other premises located at the exits of the building is not allowed.

At the beginning of the main construction work on the construction site should be provided fire-fighting water supply from fire hydrants to the existing water supply network.

Internal fire-fighting water supply and automatic fire-fighting systems, provided by the project, it is necessary to install at the same time with the installation of the object. Fire-fighting water supply system should be in effect at the beginning of departmental work, and automatic fire extinguishing and signaling systems - at the moment of start-up work. At entrances to the construction site must be installed (hung) plans of fire protection in accordance with GOST 12.1.114-82 with applied constructions and auxiliary buildings, subdivisions, constructions, assemblies. Completion of the fire shield by primary means of fire extinguishing is given in

Table 3.9 - Completion of the fire shield by primary means of fire extinguishing

| № n/n | Name of primary fire extinguishers, non-mechanized tools and inventory | Completion norms (according to PPB 01-03) |
|----------|---|---|
| 1 | Fire extinguishers: - foamy and watery place, 1 / mass of fire extinguishing composition, kg 10/9 -powder (OP) fit, 1 / mass of fire extinguishing composition, kg 10/9 | |
| 2 | Scrap | 1 |
| 3 | Bagor | 1 |
| 4 | Bucket | 2 |
| 5 | Shovel bayonet | 1 |
| 6 | Shovel sovkovaya | 1 |
| 7 | Capacity for water storage is 0.2mz | 1 |

The object must be defined face, responsible for the acquisition, repair, safety and readiness to act as a first aid in case of fire. Each fire extinguisher, installed on the object, must have a serial number, applied to the case with white paint. They will make a passport in the prescribed form. Fire extinguishers should always be in good condition, periodically inspected, checked and recharged in a timely manner.

Water storage tanks installed next to the fire shield should have a volume of not less than 0.2 m³.

The use of primary means of firefighting, unmechanized firefighting equipment and equipment for household and other needs not related to the fire is prohibited.



4 Economic part

Estimated cost - the amount of all monetary costs necessary for the implementation of construction materials on the project. Estimated cost is the basis for determining the size of capital investments, financing the construction process, the creation of contract prices for the production of construction, calculations for the contract work performed (construction). The following types of estimate documentation are presented in the diploma work:

- Local estimate - the primary document in the estimate, which is based on the volume and cost of the projected building. Local estimate

application 3.

- Sheet volume of work

The estimate was made using the resource method of determining the cost.

Table 4.1 - Construction cost

| Сме | тный | расчет | стоим | ости | СТІ | DON. | гелі | ьства |
|-----|------|--------|-------|------|-----|------|------|-------|
|-----|------|--------|-------|------|-----|------|------|-------|

| Многоэт | ажное | общежи | тие |
|---------|--------|--------|-----|
| (наимен | ование | стройк | u) |

Составлен в текущих ценах по состоянию на 2020г.

| | № смет и | Сметная стоимость, тысячи тенге | | | и тенге | |
|-----|------------------------|--------------------------------------|--------------|---------------|------------|--------------|
| № | расчетов, | Наименование глав, | строительно- | оборудования, | прочих | Всего, |
| π/π | иные | объектов, работ и затрат | монтажных | мебели и | затрат | тысячи тенге |
| | документь | | работ | инвентаря | | |
| 1 | 2 | 3 | 4 | 5 | 6 | 7 |
| | | Глава 2. Основные объекты строительс | тва | | | |
| 1 | 02-001 | Много этажное общежитие | 638 407,553 | | | 638 407,553 |
| | | Итого по главе 2 | 638 407,553 | | | 638 407,553 |
| | | Итого по главам 1 - 7 | 638 407,553 | | | 638 407,553 |
| | | Итого по главам 1 - 9 | 638 407,553 | | | 638 407,553 |
| | | Итого сметная стоимость | 638 407,553 | | | 638 407,553 |
| 2 | Кодекс РК от | Налог на добавленную стоимость (НДС) | | | 76 608,906 | 76 608,906 |
| | 10.12.2008 № | - 12 % | | | | |
| | 99-IV, ст.2 6 8 | | | | | |
| | | Всего по сметному расчёту | 638 407,553 | | 76 608,906 | 715 016,459 |


4.1 Calculation of investment costs for construction

Investment costs for construction include all costs of the customer for the project and are included in the summary estimate of the cost of construction.

The following estimates of the cost of construction include the following items:

- cost of engineering services;
- preparation of operational personnel;
- cost of design and development work;
- cost of expertise of design and estimate documentation;
- costs for the implementation of the author's supervision of SNiP RK 1.03-03-2002. The cost of design and development work is determined in accordance with the

general provisions on the definition of the cost of design work for construction in the Republic of Kazakhstan (RDS RK 08.02-03-2002 with changes from 02.7.2004)



CONCLUSION

On the basis of the assignment was a diploma project on the theme Multistorey dormitory in Taraz. In the architectural-constructive part of the diploma were considered volumetric-planning, as well as constructive decisions, issued and reviewed geological and climatic conditions, clarified the composition and methods of production, workmanship, production, workmanship.

The heat calculation was made in accordance with the applicable standards and conditions of the construction site. In the calculation-constructive section was performed work in the program "Lyra".

The calculation and design of the floor slabs with the use of the results of the calculations of the fittings, calculated as the required amount. In the division of technology and organization of construction production were calculated works relating to the underground part of the building - earthworks and concrete, selected corresponding and economically calibrated machinery. The economic indicators of the building were calculated with the help of the software package Smeta Trial, which significantly simplifies this process.

The economic side of construction was shown in local, resource and summary estimates. In the section on life safety and labor protection, the necessary conditions and rules for the management of construction work are considered, as well as the ways to reduce the negative impact of work on the environment.

In this project in architecture and construction, settlement construction and manufacturing parts made engineering decisions.

The general technical and economic parameters of the project, as well as decisions on environmental protection and safety.

LIST OF REFERENCES

- 1. SNiP 2.0107-85. Loads and effects.
- 2.SNiP 2.0107-85. Loads and effects.
- 3.SNiPRK 2.04-01-2001 "Construction climatology".
- 4. SNiP KP 2.04-03-2002 "Construction and heating equipment".
- 5. SNiP RK 5.03-33-2005 "Concrete and reinforced concrete structures".
- 6.SNiP 2.0107-85. Loads and effects.
- 7. SNiP 2.02.05-2002 "Fire safety of buildings and structures", Almaty, 2001
- 8. SNiP 2.0107-85. Loads and effects.
- 9. ENiR E4-1 "Installation of prefabricated and monolithic reinforced concrete structures".
 - 10. ENiR E2-1 "Earthworks".
 - 11. ENiR Collection E11. Construction, installation and repair work.
 - 12. PPE 2.01.02-85 Fire-fighting doses. Gosstroy USSR CITP, M, 2002 16 s.
 - 13. PPE 2.01.02-85 Fire-fighting doses. Gosstroy USSR CITP, M, 2002 16 s.
 - 14. SP RK 5.01-102-2013Based on buildings and structures. Astana, 2013.
- 15. SN RK 5.01-01-2013Earth constructions, foundations and foundations. Astana, 2013.
 - 16. Baikov VN, Sigalov EE Reinforced concrete structures: General course:
 - 17. MES RK 2.03.30-2006 "Construction in the seismic zone".
- 18. Ministry of Finance of the Republic of Kazakhstan 8.02-02-2002 "Procedure for determining the estimated cost of construction in the Republic of Kazakhstan", Almaty, 2002
- 19. NTP RK 01-01-3.1 (4.1) -2012 "Loads and effects on the building. Snow loads. Wind reactions."

Applications A

```
The calculation is performed by the software complex "LIRA-CAD 2016 R5 (non-
commercial)".
                     The basis of the calculation is the method of finite
elements
       X linear axis X
       Y linear axis Y
       Z linear axis Z
      UX angle around axis X
      UY corner circle axis Y
      UZ corner axis Z
On the PC "LIRA-CAD 2016 R5 (non-commercial)"
following normative and regulatory documents:
SP 14.13330 2011.
                                 Construction in seismic areas. Updated edition
of SNiP II-7-81 *.
SP 16.13330 2011. Steel constructions. Updated
                                                                       edition of
SNiP II-23-81 *.
SP 20.13330 2011. Loads and effects. Updated
                                                                  edition of SNiP
2.01.07-85 *.
                           Foundations
                                          of buildings
SP
      22.13330
                   2011.
                                                                      structures.
Updated
                           edition of SNiP 2.02.01-83 *.
SP 24.13330 2011. Pile foundations. Updated
                                                                  edition of SNiP
2.02.03-85.
                 SP
                          35.13330
                                                    Bridges
                                       2011.
                                                                  and
                                                                           pipes.
                           edition of SNiP 2.05.03-84.
Updated
    63.13330.2012.
SP
                     Concrete and reinforced
                                                  concrete
                                                              structures. Basic
                               Updated edition of
provisions.
SNiP 52-01-2003.
SNiP 2.03.01-84 \star. Concrete and reinforced concrete structures. SNiP II - 7-81 \star. Construction in seismic areas.
SNiP II - 23-81 *. Steel constructions.
SNiP 2.02.01-83 *. Foundations of buildings and structures.
SNiP II - 21-75. Concrete and reinforced concrete structures.
SNiP 2.05.03-84 *. Bridges and pipes.
SP 50-101-2004. Summary of rules for design and construction. Design
                   and the structure of the foundations and foundations of
buildings
                                                                      structures.
                                      and
SNiP 52-01-2003. Concrete and reinforced concrete structures. NP-031-01.
Standards for the design of seismic nuclear power plants.
Gosatomnadzor of Russia.
DBN B.2.3-14: 2006. Transportation facilities. Bridges and pipes. Design norms.
DBN B.1.2-2: 2006. Loads and effects. Design norms.
DBN B.1.1-12: 2006. Construction in seismic regions of Kazakhstan.
DBN B.2.2-24: 2009. Design of high-rise residential and civil installations.
DBN B.2.1-10: 2009. Foundations and foundations of constructions.
DBN B.2.6-98: 2009. Concrete and reinforced concrete structures.
DBN B.2.3-14: 2006. Transportation facilities. Bridges and pipes. Design norms.
DBN B.1.2-2: 2006. Loads and effects. Design norms.
DBN B.1.1-12: 2006. Construction in seismic regions of Ukraine.
DBN B.2.2-24: 2009. Design of high-rise residential and civil installations.
DBN B.2.1-10: 2009. Foundations and foundations of constructions.
DBN B.2.6-98: 2009. Concrete and reinforced concrete structures.
DSTU BV.2.6-156: 2010. Concrete and reinforced concrete structures made of heavy
DSTU 3760: 2006. Rolling reinforcement for reinforced concrete structures.
SNRA II-2.02-94. Seismic construction. Armenia.
KMC 2.01.03-96 *. Construction in seismic areas. Uzbekistan.
SNT 2.01.08-99 *. Construction in seismic areas. Turkmenistan.
Mon 01.0.1-09. Construction in seismic areas. Georgia.
AzDTN 2.3-1-2010. Construction in seismic areas. Azerbaijan.
```

SNiP RK 2.03-30-2006. Construction in seismic areas. Kazakhstan. MKS CHT 22-07-2007. Seismic construction.

Tajikistan.

The types of end elements used are specified in document 1. In this document, in addition to the number of nodes relating to the corresponding- to the existing element, as well as the number of types of hardness.

Type 10. Universal spatial rod KE.

Type 41. Universal rectangular KE shell.

Type 44. Universal quadrilateral KE shell.

Coordinates of nodes and loads assigned in the inverted documents 4,6,7, described in the right Cartesian system coordinates.

The calculation is performed on the following downloads:

| loading | 1 _ | atatia | loading |
|---------|-----|----------|---------|
| Idading | | | |
| loading | 2 - | - static | loading |
| loading | 3 - | - static | loading |
| loading | 4 - | - static | loading |
| loading | 5 - | - static | loading |
| loading | 6 - | - static | loading |
| | | | |

Calculated combinations of forces are selected for the rod on the criterion of extreme normal and propulsive stresses in the peripheral zones of the cut.

Calculation of stresses for lamellar stresses

elements are selected according to the criterion of extreme stresses taking into account the direction of the main areas.

When choosing the calculated combinations of forces were considered following characteristics of downloads:

loading 1 - static loading

This load is considered as a constant load.

loading 2 - static loading

This load is considered as a constant load.

loading 3 - static loading

This load is considered as a constant load.

loading 4 - static loading

This loading is considered to be long-lasting load.

loading 5 - static loading

This loading is considered as short-term load. loading 6 - static loading
This loading is considered as short-term

load. ЧТЕНИЕРЕЗУЛЬТАТОВСЧЕТА

Section 1. Processor operation protocol.

Section 2. Original data.

Section 3. Diagnostic messages.

Section 5. Moving nodes.

Section 6. Strength (tension) in the elements.

Section 7. Reactions in uzlah.

Section 8. Computational combinations of methods (RSU).

Section 5 is printed in tabular form nodes of the calculated task.

The size of the displacement is specified in the cap table.

The first column contains the download number and indexing number relocations.

In the remaining columns - the number of nodes in the order of age and great relocations that correspond to them. Linear shifts are considered positive if they are directed along the axis coordinates. Positive angular movements correspond to the rotation against the clockwise arrow, if you look with the end of the corresponding axis. Moves have the following indexing:

```
X linear axis X
Y linear axis Y
Z linear axis Z
UX angle around axis X
UY corner circle axis Y
UZ corner axis Z
```

Section 6 is printed in tabular form elements of the calculated task. The size of the force is specified in the cap table. The first column indicates the type of KE from the library of the end elements, the number of downloads and the indexing of the usils. The following graphs indicate: in the first line of the cap - the number of the element and the number of the cut in this element, for which the seal is printed; in the second line - the number of the first two nodes

In section 8 in the tabular form are calculated calculations combinations of force (RSU) in elements for each section and additional information on combinations usiliy.

Group B1 - includes all independent downloads due to the duration of the action except seismic and other special.

Group C1 - includes group B1 plus seismic loading.

Group D1 - includes group B1 plus special (not seismic) loading.

Group A2 - includes only continuous and long-term downloads;

types of downloads - 0, 1.

Group B2 - includes constant, long and short-term downloads (except

instantaneous); types of downloads - 0, 1, 2.

Group C2 - includes all independent downloads due to the duration of the action except seismic and other special.

Group D2 - includes group C2 plus seismic loading.

Application B

```
The calculated combinations form 4 tables of results: Table 1 - RSU calculated,
calculated by calculated values of force. Table 2 - RSU calculation lengths received to help multiplication calculations strengths corresponding to
the coefficients of longevity. Table 3 - RSU normative, received with the help
of calculation methods on corresponding load-bearing coefficients. Table 4
- RSU normative lengths received to help multiply
                                                    normative factors on the
                         coefficients
                                                    of
corresponding
                                                                    longevity.
The headings of the RSU table contain the following indexes: ELM - element
number in the scheme;
NS - the number of the calculated section in the element (all KE have a
      one calculation); CRT is a criterion number by which this combination
of methods is composed,
     in accordance with the type of
KE; ST - column number of coefficients of combinations from the table of
outgoing data of the RSU;
KS - an indication of cash in the combination of crane (K) and / or seismic
         downloads;
G - index of internal groups - A1, B1, C1, D1, A2, B2, C2, D2.
Further, the identifiers of force / stress in relation to the type of CE,
and then a list of download numbers that made up the current combination.
Znakoperemennoe loading, entered in the RSU with the opposite sign
marked with a sign '-'.
Table of results for the unified RSU is formed for each
design option by specifying the option number.
The titles of the unified RSU table contain the following indexes:
PE is a sign of elemental affiliation;
ELM is the order number of the element in the circuit or in the supplement;
NS - the number of the calculated section in the element (all KE have a rod)
     one calculation);
KRT - criterion number in accordance with the type of KE;
ST - column number of coefficients of combinations from the tables of the
original data of the RSU;
KS - an indication of cash in the combination of crane (K) and / or seismic (C)
     downloads;
G - index of internal groups - A1, B1, C1, D1, A2, B2, C2, D2.
               USILIYVKONECHNYHELEMENTAH
    Type 10. Universal spatial rod KE.
The final element perceives the following types of amplification:
    N axial force; positive sign
           becomes a stretch.
   MK torque relative to axis X1;
           a positive sign corresponds to the action of the moment
           against the clockwise arrow, if viewed from the end of the axis
X1, at the intersection, belonging to the end of the rod. MY bending moment
relative to the axis Y1
a positive sign corresponds to an action
                                                     moment against the clock
arrow, if watch with
                               end of axis Y1, at the intersection, belonging
to the end of stir-
                              жня.
    MZ bending moment relative to the Z1 axis;
       a positive sign corresponds to the action of mo-
                                                                   cop against
the clock arrow, if you watch with con-
                                                       tsar axis Z1, at the
intersection, belonging to the end of the rod.
     QY crossing force along the axis Y1;
put-
                  the body sign corresponds to the coincidence
                                                                            of
                      forces with axis Y1
directions
```

rod. QZ cutting force along the Z1 axis; put— the body sign corresponds to the coincidence of directions forces with axis Z1 for cutting, belonging to the end rod.

Type 41. Universal rectangular KE shell.



Application C

The final element perceives the following species of amphibians, stresses and reactions:

NX normal voltage along the axis X1;

a positive sign corresponds to a stretch.

NY normal voltage along the axis Y1;

a positive sign corresponds to a stretch.

NZ normal voltage along the Z1 axis (for the case flat deformation); positive sign becomes a stretch.

TXY driving tension, parallel axis X1 and lying flat, parallel X10Z1; for a positive take direction coinciding with the direction of the X1 axis, if NY coincides with the axis Y1.

MX moment, acting at the intersection, the orthogonal axis X1; positive sign corresponds to the stretching of the lower fiber (ratiobody axis $\mathbb{Z}1$).

MY moment, acting at the intersection, the orthogonal axis Y1; positive sign corresponds to the stretching of the lower fiber (ratiobody axis $\mathbb{Z}1$).

MXY torque; a positive sign corresponds to a curved diagonal—
whether 1-4, directed protrusion below (relatively axis
Z1). QX crossing force in the section, orthogonal axis X1; a
positive sign corresponds to a coincidence the direction of the force
with the direction of the axis Z1 on that part element, in which there
is a node 1.

QY intersecting force at the intersection, orthogonal positive sign corresponds to a coincidence of direction direction of the Z1 axis on that part of the element, in which the node is missing 1.

RZ jet ground support (when calculating the shell on the basis of

RZ jet ground support (when calculating the shell on the basis of elasticity); positive force acts in the direction of the Z1 axis (soil is stretched).

Type 44. Universal quadrilateral KE shell. The final element perceives the following species of amphibians, stresses and reactions: NX normal voltage along the axis X1; a positive sign corresponds to a stretch. NY normal voltage along the axis Y1; a positive sign corresponds to a stretch. NZ normal voltage along the Z1 axis (for the case flat deformation); positive sign becomes a stretch.

TXY driving tension, parallel axis X1 and lying flat, parallel X10Z1; for a positive take direction coinciding with the direction of the X1 axis, if NY coincides with the axis Y1.

MX moment acting on the intersection, orthogonal axis X1; a positive sign corresponds to a stretch lower fiber (relative to the Z1 axis). MY moment acting on the intersection, orthogonal axis Y1; a positive sign corresponds to a stretch lower fiber (relative to the Z1 axis). MXY torque; a positive sign corresponds to a curved diagonal— whether 1-4, directed protrusion below (relatively axis Z1).

QX crossing force in the section, orthogonal axis X1; a positive sign corresponds to a coincidence the direction of the force with the direction of the axis Z1 on that part element, in which there is a

node 1. QY intersecting force at the intersection, orthogonal axis Y1; a positive sign corresponds to a coincidence the direction $\frac{1}{2}$

Calculation protocol

Date: 16.04.2020

Genuin eIntel (R) Core (TM) i5-8250U CPU @ 1.60GHz 8 threads

Microsoft Windows 10 RUS 64-bit. Build 17763

Size of available physical memory = 4358876672

22:44 Reading the source data from the file C: \ Users \ Public \ Documents \ LIRA SAPR \ LIRA SAPR 2016 Noncommercial \ Data \ Babur calculation · .txt

22:44 Control of source data source schemes Number of nodes = 11964 (of them the number of failed nodes = 11964)

Number of elements = 12444 (of them the number of failed = 12444)

BASIC SCHEME 22:44 Optimization of unknown order Number of unknowns = 52809 CALCULATION OF STATISTICAL DOWNLOADS 22:44 Forming a stiffness matrix 22:44 Formation of load vectors 22:44 Exposition of the stiffness matrix

22:44 Calculation of unknowns 22:44 Solution control Formulation of results 22:44 Formation of topology

22:44 Optimization of unknown order Number of unknowns = 52809

CALCULATION OF STATIC LOADING 22:44 Forming a stiffness matrix

22:44 Formation of load vectors

22:44 Exposition of the stiffness matrix

22:44 Calculation of unknowns

22:44 Solution control Formulation of results

22:44Formationtopology

22:44 Formation of movements

22:44 Calculation and formation of forces in elements

22:44 Calculation and formation of reactions in elements

22:44 Calculation and formation of epyur usiliy in rods

22:44 Calculation and formation of curves of curves in rods Total node loads on the main scheme:

Loading 1 PX = 0 PY = 0 PZ = 9096.81 PUX = 2.79932e-014 PUY = -9.53196e-014 PUZ = 0

Loading 2 PX = 0 PY = 0 PZ = 8167 PUX = 2.65517e-014 PUY = -1.06207e-013 PUZ = 0

Loading 3 PX = 0 PY = 0 PZ = 2624 PUX = 0 PUY = 0 PUZ = 0

Load 4 PX = 0 PY = 0 PZ = 1530.6 PUX = 1.77011e-014 PUY = -4.42528e-014 PUZ = 0

Loading 5 PX = 0 PY = 0 PZ = 2040.8 PUX = 4.42528e-014 PUY = -7.9655e-014 PUZ = 0 Loading 6 PX = 0 PY = 0 PZ = 612 PUX = 0 PUY = 0 PUZ = 0 The calculation is successfully completed Lost time = 0 min




Figure C.1 - Calculation scheme




Figure C.2 – Hardness




Figure C.3 - Spatial model




Figure C.4 - Mosaic movement from the RSN on the X axis



Figure C.5 - Mosaic of moving from RSN on axis Y.




Figure C.6 - Mosaic movement from RSN on axis \boldsymbol{Z}




Figure C.7 - Construction. Percentage reinforcement of the column




Figure C.8 - Construction. Percentage reinforcement of crossbars




Figure C.9 - Construction. Percentage reinforcement of the column




Figure C.10- Construction. Percentage reinforcement of crossbars




Figure C.11- Construction. Column




Figure C.12 - Construction. Riegel



Application D

Estimate PK 2018 Trial - 1 - 16 CPB 02-001-001

Application 11
to the State standard on determination
of the estimated cost of construction in
the Republic of Kazakhstan
form

Name of

Construction Multi-storey dormitory. In . Taraz City

Name of the Object Multi-story Hostel

Summary resource sheet № 02-001-001 on the building, construction, object, construction

Social work

Basis:

(naming of buildings, constructions, objects, constructions)

Local resource sheets

| № п/п | Resource co | odes | Name of resources | Unit | 0,22 | ount | Cost, thou | sand tenge |
|-----------------|---------------------------|------|--|-----------|------|--------|-----------------------|------------|
| 11/11 | | | | measuring | alli | | per unit measuring | common |
| 1 | 2 | | 3 | 4 | | 5 | 6 | 7 |
| | | | Labor | costs | | | | |
| 1 | 0101-0101-0 | | | | 3184 | 8.6474 | 1.24800 | 39747.112 |
| | | | Labor costs of construction workers | person-h | | | | |
| 2 | 0101-0101-0 |)131 | (average rank 4) | person-h | 3714 | 4.908 | 1.06500 | 39559.327 |
| | | | Labor costs of construction workers | | | | | |
| 3 | 0101 0101 0 | | (average grade 3.1) Labor costs of construction workers | person-h | 1563 | 5.9023 | 1.14700 | 17934.380 |
| 3 | 0101-0101-0 | | (average grade 3.5) | person-ii | 1303 | 0.9025 | 1.14700 | 17954.500 |
| | | | | | | | | |
| 4 | 0101-0101-0 | | Labor costs of construction workers | person-h | 6384 | 1.8736 | 1.08100 | 6902.048 |
| | | | (average grade 3.2) | | | | | |
| 5 | 0101-0101- <mark>0</mark> | | | person-h | 14 | 46.7 | 1.33600 | 1932.791 |
| | | | Labor costs of construction workers (average grade 3.3) | | - 4 | | | |
| 6 | 0101-0101-0 | | Labor costs of construction workers | person-h | 878 | .7736 | 1.04500 | 918.318 |
| | | | (average rank 3) | | | | | |
| 7 | 0101-0101 -0 |)139 | | person-h | 380 | .9375 | 1.22900 | 468.172 |
| , | 0101 0101 0 | | Labor costs of construction workers | person n | | | | |
| 0 | 0101 0101 0 | | (average grade 3.9) | , | 004 | 1007 | 4 00000 | 220 542 |
| 8 | 0101-0101-0 | | Labor costs of construction workers | person-h | 234 | .4027 | 1.00900 | 236.512 |
| | | | (average grade 2.8) | | | | | |
| 9 | 0101-0101-0 | | Labor costs of construction workers | person-h | 189 | .0313 | 1.20900 | 228.539 |
| | | | (average grade 3.8) | | | | | |
| 10 | 0101-0101-0 |)120 | Затраты труда рабочих-строителей | person-h | 113 | .2215 | 0.87400 | 98.956 |
| | | | (средний разряд 2) | | | | | |
| 11 | 0101-0101-0 |)114 | Labor costs of construction workers | person-h | 0.1 | 509 | 0.79000 | 0.119 |
| | | | (average grade 1.4) | r | | | | - 113 |
| 12 | 0101 0102 0 | 1100 | Labor costs of drivers | norcen k | 5077 | 7.9919 | | |
| 12 | 0101-0102-0 | 1100 | Labor costs of drivers | person-h | 3211 | פו שנ. | | - |

| | | Weighted average job category 3.5 Total PHOT: | | | | 108026.274 |
|------|-----------------|---|-------------------|-------------------|----------|---------------------------------------|
| | | Machines and mec | hanisms by ty | / pe | | |
| | | Bulldo | zers | | | |
| 1 | 3101-0101-0103 | 1 | Car-h | 14.137652 | 4.70700 | 66.546 |
| | | Bulldozers, 79 kW (108 h.p.) | | | | |
| | 12101 0102 0104 | Scrap | | 1 4 0 40 400 | 0.004001 | 4.4-4 |
| 2 | 3101-0102-0104 | Trailed scrapers with caterpillar tractor, 8 m3 | Car-h | 1.643166 | 8.62400 | 14.171 |
| | | -2 | <u>-</u> | | 16 (| CPB 02-001-001 |
| QUE: | STION PK 2018 T | 3 | 4 | 5 | 6 | 7 |
| | | Crawler Ex | cavators | | | · · · · · · · · · · · · · · · · · · · |
| 3 | 3101-0201-0906 | | Car-h | 26.387325 | 14.65600 | 386.733 |
| | | | | | | |
| | | Mortar F | Pumps | | _ | |
| 4 | 3103-0205-0201 | Mortar pumps, 1 m3 / h | Car-h | 826. 965 | 1.21300 | 1003.109 |
| | | Vibra | tors | | | |
| 5 | 3104-0101-0201 | Surface vibrator | Car-h | 1276.8588 | 0.01500 | 19.153 |
| 6 | 3104-0101-0101 | | Car-h | 55.450643 | 0.03900 | 2.163 |
| | ı | Mobile and station | ory towar cran | 0.5 | l | |
| 7 | 3105-0101-0102 | Tower cranes, 8 t | Car-h | 3985.900736 | 5.93900 | 23672.264 |
| 8 | 3105-0101-0401 | Concrete laying tower cranes when working on hydropower construction, 10- | Car-h | 29.0 52864 | 6.96900 | 202.469 |
| | | 25 t | | | | |
| 9 | 3105-0101-0401 | | Car-h | 10.8 7578 | 6.95500 | 75.641 |
| | | Concrete laying tower cranes when working on hydropower construction, 10- | | | | |
| | | 25 t | | | | |
| | | Jib cranes of | n the road | | | |
| 10 | 3105-0102-0102 | Truck-mounted cranes, 10 t | Car-h | 56.171014 | 4.83700 | 271.699 |
| 11 | 3105-0102-0102 | | Car-h | 39.7417 | 5.20700 | 206.935 |
| 12 | 3105-0102-0202 | | Car-h | 5.06736 | 4.83100 | 24.480 |
| | ` | Cranes on the road while working on hydropower construction, 10 t | | | | |
| 13 | 3105-0102-0202 | Cranes on the road while working on hydropower construction, 10 t | Car-h | 0.71484 | 4.82800 | 3.451 |
| | | | ·1 | | | |
| 1.4 | 2105 0501 0101 | Forklift trucks, 5 t | | 9.246149 | 4.43000 | 40.960 |
| 14 | 3103-0301-0101 | Forkint trucks, 5 t | Car-h | 9.240149 | 4.43000 | 40.900 |
| | 10105 0505 045 | Lifts, towers, cradle | | | 0.000001 | 005 500 |
| 15 | 3105-0602-0401 | Mast hoists, lifting height 50 m | Car-h | 109.089 | 2.06800 | 225.596 |
| | | | | | | |
| | | Other electrica | | | | |
| 16 | 3106-0103-0301 | Welding transformers with a rated | Car-h | 2432.3328 | 0.13600 | 330.797 |
| | | welding current of 315-500 A | | | | |

| 17 | 3106-0103-0301 | Welding transformers with a rated | Car-h | 36.45684 | 0.12500 | 4.557 |
|-------|----------------|---|-----------------------------------|---------------------|---------|----------------|
| 18 | 3106-0103-0501 | Direct current installations for manual arc | Car-h | 21.110205 | 0.17600 | 3.715 |
| | | welding | | | | |
| 19 | 3106-0202-0501 | Other equipment for v | welding and cut Car-h | tting 57.43008 | 0.02600 | 1.493 |
| 17 | 3100 0202 0301 | Apparatus for gas welding and cutting | | 07.10000 | 0.02000 | 1. 100 |
| | ' | Self-propelled | road rollers | | • | |
| 20 | 3201-0101-0102 | Rollers road self-propelled smooth, 8 t | Car-h | 2.171326 | 3.75200 | 8.147 |
| | | Trailed roa | d rollers | | | |
| 21 | 3201-0102-0301 | Trailed road rollers on pneumatic wheels, 25 t | Car-h | 0.4485 | 0.73600 | 0.330 |
| 22 | 3201-0102-0201 | Trailed cam rollers, 8 t | Car-h | 2.171326 | 0.11500 | 0.250 |
| | I | Bitumen | l boilers | | | |
| 23 | 3201-0201-0101 | Mobile bitumen boiler 4001 | Car-h | 108.998437 | 0.75300 | 82.076 |
| 24 | 3201-0201-0101 | Mobile bitumen boilers, 400 l | Car-h | 8.3398 | 0.72300 | 6.030 |
| | ' | Road marking, marking, v | vater-washing r | nachines | ' | |
| 25 | 3201-0211-0201 | | Car-h | 0.009222 | 5.58700 | 0.052 |
| | TA PK 2018 | Water-jetting machines, 6000 1 | | | 16 (| CPB 02-001-001 |
| Trial | 2 | 3 | 4 | 5 | 6 | 7 |
| | | Machines for plantin | ng plants <mark>and</mark> ot | her | | |
| 26 | 3206-0102-0701 | Mounted brush cutters on a tractor, 79 kW (108 h.p.) with hydraulic control | Car-h | 0.39123 | 5.62600 | 2.201 |
| | | Dump t | l rucks | | | |
| 27 | 3301-0101-0101 | Dump trucks, 7 t | Car-h | 16.8912 | 3.26500 | 55.150 |
| 28 | 3301-0101-0101 | Dump trucks, 7 t | Car-h | 3.21678 | 3.26700 | 10.509 |
| | | On-boar | d cars | | | |
| 29 | 3301-0201-0101 | | Car-h | 83.286609 | 2.63200 | 219.210 |
| 30 | 3301-0201-0101 | | Car-h | 19.593792 | 2.62700 | 51.473 |
| 31 | 3301-0201-0101 | | Car-h | 8.3398 | 2.89100 | 24.110 |
| | | Onboard vehicles, up to 5 t Crawler t | ractors | | | |
| 32 | 3304-0101-0102 | 2 | Car-h | 2.619826 | 4.45000 | 11.658 |
| | | Tracked tractors, 79 kW (108 h.p.) | | | | |
| 33 | 3304-0101-0101 | Crawler tractors, 59 kW (80 h.p.) | Car-h | 0.092219 | 3.92200 | 0.362 |
| | | Cutting | l g tool | | | |
| 34 | 3403-0102-0102 | Electric submersible saw, 1.4 kW | Car-h | 104.6178 | 0.04000 | 4.185 |
| 35 | 3403-0102-0201 | Electric chain saws | Car-h | 7.2335 | 0.07500 | 0.543 |
| | • | Plane | ers | . ' | Į. | |
| 36 | 3403-0201-0101 | | Car-h | 13.616 | 0.12200 | 1.661 |

| | | Hammers, drills, screwdrivers, | wrenches, cons | struction guns | | |
|-----|-----------------|---|-----------------------|----------------------------|-----------|----------------|
| 37 | 3403-0302-0101 | Electric rotary hammer | Car-h | 1175.7048 | 0.01800 | 21.163 |
| 38 | 3403-0302-0301 | Electric drills | Car-h | 547.998 | 0.01300 | 7.124 |
| 39 | 3403-0302-0701 | Electric wrench | Car-h | 159.4176 | 0.03600 | 5.739 |
| 40 | 3403-0302-0501 | Construction screwdrivers | Car-h | 338.7624 | 0.01600 | 5.420 |
| 41 | 3403-0302-0301 | <u> </u> | Car-h | 71.6542 | 0.01200 | 0.860 |
| | | Electric drills | | | | |
| 42 | 3403-0401-0101 | Моло Riveting hammers | тки Car-h | 1135.8504 | 0.06000 | 68.151 |
| | | Total for construction machines and | | | | 27142.336 |
| | | mechanisms: including pay for drivers | | | | |
| | | Contractor Sup | Tenge oply Materials | | | 6480.144 |
| | | | | | | |
| 1 | 2101-0201-0604 | Dense rock crushed stone Crushed stone from dense rocks for | e for construction M3 | on work 0. 225 | 2.31200 | 0.520 |
| | | construction works M1000, fraction 40-70 mm ST RK 1284-2004 | | | | |
| | 1 | Dense rock gravel for | r construction w | vork | | |
| 2 | 2101-0301-0101 | Gravel for construction work M1000, | м3 | 6.5 625 | 3.84200 | 25.213 |
| | | fraction of 5-10 mm ST RK 1284-2004 | | | | |
| 3 | 2102-0101-0601 | General purpo | ose concrete M3 | 3015.2199 | 16.89700 | 50948.171 |
| 4 | | Heavy concrete B3,5 GOST 7473-2010 | м3 | 66.3255 | 11.43400 | 758.366 |
| | | Mortar so | | | | |
| 5 | 2102-0401-2808 | The solution is ready masonry heavy cement-lime grade M25 GOST 28013-98 | м3 | 336.6 | 13.43700 | 4522.894 |
| | | | | | | |
| | | Finishing s | solutions | | | |
| CME | TA PK 2018Trail | -4 | | | 16 0 | CPB 02-001-001 |
| 1 | 2 | 3 | 4 | 5 | 6 | 7 |
| 6 | 2102-0402-0206 | The solution is finished finishing heavy, cement-lime 1: 1: 6 GOST 28013-98 | м3 | 231.03 | 17.52300 | 4048.339 |
| | | Ceramic | brick | | ļ | |
| 7 | 2103-0101-0103 | | 1000 шт. | 0.37 | 25.99600 | 9.619 |
| | | Brick ceramic unary ordinary corpulent brand M100, dimensions 250 mm x 120 mm x 65 mm GOST 530-2012 | | | | |
| | 1 | Stones and blocks ma | ide of natural et | tone | | |
| 8 | 2103-0499-9903 | | м2 | 4332.0 | ı I | |
| 0 | 2103-0499-9903 | Straight stone facing | MZ | 4332.0 | - | |
| | 10105 0001 0000 | Fittii | | 070 4 | 040 40000 | 70000 700 |
| 9 | 2105-0301-3202 | Hot-rolled reinforcing steel of a periodic profile of class A-III (A400) with a diameter of 14 to 32 mm ST RK 2591- | Т | 379.4 | 210.42900 | 79836.763 |
| 10 | 2105-0301-3002 | 2014 Hot-rolled smooth reinforcing steel, class AI (A240) with a diameter of 14 to 25 mm | Т | 45.23904 | 219.31500 | 9921.600 |
| | | ST RK 2591-2014 | | | | |
| ! | I | Win | l re | I | I | |
| • | | | | | | ı |

| 11 | 2105-0307-1007 | Wire of low carbon light steel, general purpose, superior quality, heat treated, diameter 1.1 mm GOST 3282-74 | кг | 1380.672 | 0.11200 | 154.635 |
|----|--------------------|---|-------------------|-----------------------|--------------------|--------------------|
| 12 | 2105-0307-1007 | Wire of low carbon light steel, general purpose, superior quality, heat treated, diameter 1.1 mm GOST 3282-74 | Kg | 349.128 | 0.11200 | 39.102 |
| 13 | 2105-0307-1013 | Hot-rolled wire of ordinary accuracy in coils of steel SV-08A with a diameter of 6.3 mm to 6.5 mm GOST 10543-98 | Kg | 43.5438 | 0.07000 | 3.048 |
| | | | | | | |
| 14 | 2105-0308-1202 | Mesh steel wicker, Woven grid with square cells of group 2 without coating of low-carbon wire GOST 3826-82 | woven, twisted M2 | 323 <mark>1.36</mark> | 1.34800 | 4355.873 |
| 15 | | Woven wire mesh with square cells 5 mm x 5 mm, of carbon steel of ordinary quality, uncoated, 1.6 mm in diameter GOST 3826-82 | м2 | 423.81 | - | |
| | | Other constructions, materi | als, products ar | nd details | | |
| 16 | 2106-0510-5501 | Steel Scaffolding Parts | T | 1.887 | 435.70900 | 822.183 |
| 17 | 2106-0510-2602 | Rods and Anchors | Т | 2.0424 | - | - |
| S | eparate structural | elements of buildings and structures (colum | nns, beams, trus | sses, communic | ations, crossbars. | , racks, etc.) |
| 18 | | Seperate structural elements of buildings and structures with a predominance of hot-rolled profiles | Т | 11.25 | 463.20300 | 5211.034 |
| | | Лесомат ериалы к т | руглые (бревна | Ĺ | | |
| 19 | 2107-0101-9901 | Round soft wood construction from 140mm to 240 mm thick from 3m to 6m from GOST | м3 | 13.098 | 31.57200 | 413.530 |
| | TA DI | Edged bars | | | 40.4 | |
| 1 | TA PK 2018 Trail | -5 | 4 | 5 | 6 | 7 7 CPB 02-001-001 |
| | 2107-0201-0301 | 3 | м3 | 144.39 | 25.44300 | 3673.715 |
| 20 | | Coniferous edged beams from 4 m to 6.5 m long, from 75 mm to 150 mm wide, from 40 mm to 75 mm thick, 3 grades GOST 8486-86 | | 4 | | |
| 21 | 2107-0201-0203 | | м3 | 22 .275 | 56.99700 | 1269.608 |
| | | Coniferous edged boards from 4 m to 6.5 m long, from 75 mm to 150 mm wide, 150 mm and more thick, 2 grades GOST 8486-86 | | | | |
| 22 | 2107-0201-0201 | Coniferous edged bars with a length of 4 m to 6.5 m, a width of 75 mm to 150 mm, a thickness of 40 mm to 75 mm, 2 grades GOST 8486-86 | м3 | 7.474 | 47.24500 | 353.109 |
| 23 | | Coniferous edged bars from 4 m to 6.5 m long, from 75 mm to 150 mm wide, from 40 mm to 75 mm thick, 4 grades GOST 8486-86 | м3 | 1.53 | 18.35800 | 28.088 |
| | ı | Доски об | резные | ı | l | |

| 24 | | Coniferous edged boards up to 6.5 m long, from 75 mm to 150 mm wide, 44 mm thick or more, 3 grades GOST 8486-86 | м3 | 71.54976 | 47.43400 | 3393.891 |
|-----|------------------|---|--------------------------|----------------|-----------|----------------|
| 25 | 2107-0203-0302 | Coniferous edged boards up to 6.5 m long, from 75 mm to 150 wide, mm from 19 mm to 22 mm thick, 3 grades GOST | м3 | 19.166 | 47.48400 | 910.078 |
| 26 | 2107-0203-0303 | Coniferous edged boards up to 6.5 m long, from 75 mm to 150 mm wide, 25 mm thick, 3 grades GOST 8486-86 | м3 | 11.925 | 47.43400 | 565.650 |
| 27 | 2107-0203-0204 | Coniferous edged boards up to 6.5 m long, from 75 mm to 150 mm wide, from 32 mm to 40 mm thick, 2 grades GOST | м3 | 5.8752 | 52.85300 | 310.522 |
| 28 | | Coniferous edged boards up to 6.5 m long, from 75 mm to 150 mm wide, from 32 mm to 40 mm thick, 3 grades GOST 8486-86 | M3 | 5.92 | 47.48400 | 281.105 |
| 29 | 2107-0510-1003 | | м2 | 11250.0 | 15.70700 | 176703.750 |
| 30 | 2107-0510-0701 | Inventory racks wood-metal sliding | шт. | 63.0 | 20.70200 | 1304.226 |
| 31 | 2107-0510-0201 | Wooden scaffolding parts GOST 8242-88 | м3 | 0.306 | 31.41500 | 9.613 |
| 32 | 2110-0401-0101 | Ruberoid, glassruberoi Roofing roofing material with coarse- grained powdering RKK-350B GOST | м2 | 2875.0 | 0.24100 | 692.875 |
| 33 | | Waterproofir Roofing mastic for hot application MBK- G GOST 2889-80 | ng mas tics Kg | 78 75.0 | 0.13200 | 1039.500 |
| 34 | | Mastic frost-resistant bituminous and oil MB-50 GOST 30693-2000 Lim | Kg | 3750.0 | 0.22400 | 840.000 |
| CME | TA PK 2018 Trial | - 6 - | | | 16 (| CPB 02-001-001 |
| 1 | 2 | 3 | 4 | 5 | 6 | 7 |
| 35 | | Building quicklime lump, grade 1, GOST 9179-77 Gypsi | T | 1.97769 | 31.76800 | 62.827 |
| 36 | 2113-0103-0102 | Plaster binders GOST 125-79 brand G-3 | Т | 0.918 | 22.19400 | 20.374 |
| 37 | 2113-0104-0103 | Bitumen oil construction GOST 6617-76 brand BN 90/10 | Т | 0.25 | 140.31300 | 35.078 |
| 38 | | Болты строительные с гайками с шестигранной головкой ГОСТ 1759.0- 87 Nail | T | 0.05402 | 456.85200 | 24.679 |
| 39 | 2113-0209-0104 | | Kg | 1967.4648 | 0.37200 | 731.897 |
| 40 | 2113-0209-0104 | Construction nails GOST 283-75 | кg | 94.72 | 0.27800 | 26.332 |
| ŀ | I | Technical | l gases | I | ļ | |
| I | | | | | | I |

| 41 | 2113-0701-0401 | Technical gaseous oxygen GOST 5583-78 | м3 | 45.5328 | 0.26600 | 12.112 |
|----|-----------------|---|----------------|---------------------|------------|----------|
| 42 | 2113-0701-1002 | Propane-butane, mixture technical GOST | КГ | 14.688 | 0.14400 | 2.115 |
| | | R 52087-2003 Oil: | s | | | |
| 43 | 2113-0702-0201 | | Т | 0.09324 | 408.08400 | 38.050 |
| | | Diesel engine oil M-10DM GOST 12337- 84 | | | | |
| 44 | 2113-0702-0101 | Anthracene oil GOST 11126-88 | T | 0.646272 | 44.84000 | 28.979 |
| | | Technical | l fluids | | | |
| 45 | 2113-0703-0201 | | Т | 0.375 | 53.70000 | 20.138 |
| 46 | 2113-0703-1405 | Kerosene for technical purposes of the grades KT-1, KT-2 | 1 м3 | 88.88052 | 0.08600 | 7.644 |
| | | Technical water | | | | |
| 47 | 12112 0002 1101 | Fabri | | 1 20 74 <i>5</i> 75 | 0.004.00 | 200 220 |
| 47 | 2113-0803-1101 | Ткань мешочная ГОСТ 30090-93 | 10 м2 | 38.71575 | 6.93100 | 268.339 |
| | | Components, consu | mables for too | ls | | |
| 48 | 2113-0812-1035 | Electrodes, d = 4 mm, E42 GOST 9466- | T | 0.58752 | 211.19100 | 124.079 |
| 49 | 2113-0812-1035 | | T | 0.052425 | 211.19200 | 11.072 |
| | | Electrodes, d = 4 mm, E42 GOST 9466- Other ma | terials | | | |
| 50 | 12112 0016 2000 | Polypropylene plate holder for thermal | | l 361 72.2 | 0.02100 | 759.616 |
| 30 | 2113-0810-2808 | insulation with a plastic core made of polyamide 10x200 mm | peci. | 30172.2 | 0.02100 | 739.010 |
| 51 | 2113-0816-2806 | | peci. | 14468.88 | 0.01700 | 245.971 |
| | | Polypropylene plate-shaped holder of thermal insulation with a plastic core made of polyamide 10x160 mm | | | | |
| 52 | 2113-0816-9902 | Antiseptic paste | Т | 0.07881 | 605.54700 | 47.723 |
| 53 | 2113-0816-2701 | | Т | 0.19684 | 80.24400 | 15.795 |
| 54 | 2113-0816-3526 | Coal tar | Т | 0.00625 | 1152.69600 | 7.204 |
| | | Simazin 50% wettable powder GOST 15123-78 | | | | |
| | 10000 1101 1101 | Paronite g | gaskeis | 05.004 | | 105 107 |
| 55 | 2302-1101-1401 | Gaskets paronite GOST 481-80 | кд | 95.304 | 1.42100 | 135.427 |
| | | Petro | ol | | ! ! | |
| 56 | 2601-0101-0102 | | Кд | 8.8128 | 0.19200 | 1.692 |
| | | AI-92 gasoline | 6 | 7 | | |
| | | Shields of formy | work, flooring | | | |
| 57 | 2701-0101-0104 | | м2 | 1937.25 | 0.89100 | 1726.090 |
| 58 | 2701-0101-0102 | | м2 | 95.76576 | 3.30300 | 316.314 |
| | I | | | I | I | |

| 1 | 2 | | 3 | 1 9 3 | A 4 | 5 | 6 | 7 |
|----|----------------|---------------------------|-------------|-------|------------|---------|---------|------------|
| 59 | 2701-0101-0102 | Flooring shields | | 1 / 3 | M2 | 72.8328 | 3.30300 | 240.567 |
| 60 | 2701-0101-0105 | Boards from boards, thick | kness 40 mm | | м2 | 15.3684 | 1.25500 | 19.287 |
| | | Total contractor supply m | naterials: | | | | | 357376.021 |
| | | Total | | | | | | 492544.631 |

| Compiled | | |
|----------|--|--|
| | position signature (initials, last name) | |
| Checked | position, signature (initials, surname) | |

| СМЕТА РК 2018 Триал | | 1 9 3 4 | | | | | to the normati | Apperive document cost of constr | ndix 2 for the determ uction in the R | epublic of |
|---|-------------------|------------|------------------|----------------------|--------------|-------------------------------------|-----------------|----------------------------------|---|--|
| Construction Name Multi-storey dormitory | | | | | | | | | | Форма 4 |
| Object name Multi-storey HOstel | | | | | | | | | | |
| | Lo | cal budget | number | 02-001-001 | (Local cos | st estimate |)) | | | |
| on | | | Genera | al construction | work | | | | | |
| | | | (name c | f work and cos | its) | | | | | |
| Base: | | | | | | | | | | |
| | | | | | | Estimated cost imated salary | | C | | |
| | | | | | Normativ | ve labor input | 99535.53 | person-hours month | / 164 = 606.9 | 92 hours / |
| | | | | 1 | Machines and | l mechanisms | | • | | |
| | | | | | Materials a | nd equipment | 357376020 | | | |
| | | | | | | mer Materials her equipment | | Tenge Tenge | | |
| Compiled at current prices as of 2020. | | | | | Custom | ici equipment | | - | | |
| № п/п Code number resource code Name work and costs | Unit measuring | amount | Unit co Total | exploitation of cars | Total | Total cost, ten эксплуатац ия машин | ge материалы | Overhead, tenge | Total cost with NR and SP, tenge | Labor costs of construction workers, total |
| | | | the salary | including | the salary | including | equipment, | Estimated | | |

| | 1 | | | 1 | working | the salary | working | the salary | furniture, | profit, tenge | | Labor costs |
|-----|----------------|--|-----------------|-----------------|------------------|----------------|-----------------------|---------------|----------------|-----------------|-------------|--------------|
| | | | | | builders | drivers | builders | drivers | inventory | prom, tenge | | of drivers. |
| | | | | | bullders | directs | bullders | directs | inventory | | | total |
| | | | | | 9 | 3 4 | | | | | | totai |
| 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 |
| 1 | | _ | • | | | | | | 10 | 11 | 12 | 13 |
| | | Coif. to take into account the infl | uence of the | conditions of | construction a | nd special co | nstruction wo | rks: | 11.1 | | | |
| | | 1.15 - Construction of engineerin | g networks a | and structures, | as well as hou | sing and civil | facilities in | the cramped c | onditions of t | he built-up par | t of cities | |
| | | | | | | | | | | | | ļ i |
| | | Section No. 1 Earthwork | | | | | | | | | | |
| | 4440 | | 2 | 7400 | 5740 07 | 004.54 | 405 4000 | 0.40400 | 0004070 | 1 4007004 | 0500040 | 4440.70 |
| 1 | | Fences are deaf. Poal Mounting Devices | м2 the fence | 740.0 | 5749. 87 | 324.51 | 4254900 | 240139 | 2081970 | 1827831 | 6569349 | 1446.70 |
| | 0101 | Devices | the felice | | 2611.88 | 132.61 | 1932791 | 98132 | - | 486618 | | 48.08 |
| CME | Ι ΓΑ PK 201 | L | | | | - 2 - | | | | | 16_л | c 02-001-001 |
| 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 |
| 2 | 4404 | | | 0.00 | 04450.00 | 04450.00 | | 2004 | | | | |
| 2 | 1101- 0207- | Shrubs and dense forests are dense. Cutting in soil of natural | га | 0.09 | 2445 6.22 | 24456.22 | 2201 | 2201 | - | 508 | 2926 | - |
| | 1301 | occurrence by brush cutters on a | | | - | 7828.95 | - | 705 | - | 217 | | 0.39 |
| | | tractor 79 kW (108 l s) | | | | | | | | | | |
| | | (11) | | | | | | | | | | |
| | | | | | | | | | | | | |
| 3 | 1101- 0102- | Soils of 2 groups. Development | м3 soil | 1875.0 | 204.32 | 199.04 | 3 <mark>83</mark> 108 | 373203 | 520 | 45704 | 463117 | 10.74 |
| | 0320 | with loading on dump trucks by HITACHI excavators with a | SOII | | 5.01 | 28.85 | 9385 | 54093 | - | 34305 | | 53.50 |
| | | bucket with a capacity of 1 m3 | | | | 1 | | | | | | |
| | | sucher with a capacity of 1 ms | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| 4 | 1101- | | м3 soil | 312.0 | 155.98 | 151.69 | 48666 | 47327 | - | 5110 | 58078 | 1.53 |
| | 0101- 0320 | Soils of 2 groups. Development | | | 4.29 | 18.45 | 1339 | 5758 | ļ | 4302 | | 6.46 |
| | 0320 | into a dump with HITACHI | | | 7.29 | 10.43 | 1339 | 3730 | | 4302 | | 0.40 |
| | | excavators with a bucket with a | | | | | | | | | | |
| | | capacity of 1 m3 | | | | | | | | | | |
| 5 | 1101- | | м3 soil | 72.9 | 3244.34 | | 236512 | - | | 170289 | 439345 | 234.40 |
| | | | | 1 | | | | | | | | |

| ĺ | 0205- | Soils of 2 groups. Manual | | 1 | 3244.34 | - | 236512 | - | - | 32544 | Ī | - |
|-----|------------------------|--|---------------|--------|-----------|----------------|-----------------|--------|----------|---------|----------|------------|
| | 0202т.11. п.3.179К= | development with fastenings in | | | | | | | | | | |
| | 1.2 | trenches more than 2 m wide | | | 1 4 3 | - 4 | | | | | | |
| | | and pits with a cross-sectional | | | | | | | | | | |
| | | area of up to 5 m2, depth up to 2 | | | | | | | | | | |
| | | m [Manual refinement, | | | | | | | | | | |
| | | cleaning of the bottom and walls | | | | | | | | | | |
| | | with soil dumping in pits and | | | | | | | | | | |
| | | trenches, developed by a mechanized method | | | | 1 | | | | | | |
| | | mechanized methodj | | | | | | | | | | |
| 6 | 1101- | Ground pillows on subsiding | мЗsoil | 72.9 | 515.79 | 513.81 | 37 602 | 37458 | 25 | 8266 | 49537 | 0.15 |
| 0 | 0201- | soils. The device by layered | MSSOII | 12.9 | | | | | 2.5 | | 49337 | |
| | 1001 | rolling | | | 1.64 | 15 5.82 | 119 | 11361 | - | 3669 | | 7.11 |
| | | | | | | | | | | | | |
| 7 | 1101- | | м3 soil | 312.0 | 20.57 | 20.57 | 6418 | 6418 | - | 1750 | 8821 | - |
| | 0104- 0405 | Trenches and pits. Filling with | | | | 7.79 | - | 2431 | - | 653 | | 1.36 |
| | | bulldozers with a capacity of | | | | - 1 | | | | | | |
| | | 79 kW (108 l s) when | | | | | | | | | | |
| | ļ | moving soil up to 5 m. | | | | | | | | | | |
| 8 | 1101- 0201- | | м3 soil | 312.0 | 76.42 | 76 .42 | 23 842 | 23842 | - | 6350 | 32607 | = |
| | 0102 | Priming. Sealing with trailed | SOII | | 4 | 28.27 | - | 8819 | - | 2415 | | 5.02 |
| | | rollers on pneumatic wheels | | | | | | | | | | |
| | | 25 tons. First pass along | | | | | | | | | | |
| | ļ | one track with a layer | | | | V | 1000010 | | | | | 1000 50 |
| | | Section total | | | | | 499 3249 | 730588 | 2082515 | 2065808 | 7623780 | 1693.52 |
| | | No 1 | | | | | 2180146 | 181299 | - | 564723 | | 121.92 |
| CME | I TA PK 201 | 8 Trail | | | - 3 - | | | | I | I | 16_л | 02-001-001 |
| 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 |
| | | | | | | | | | | | ı | |
| 9 | 1108- | Section No. 2 Foundations | 2 | 1562.5 | 005 54 | 22.94 | 1399231 | 35843 | 895216 | 439571 | 1985906 | 380.94 |
| 9 | 0101- | Walls, foundations. | м2 surface | 1562.5 | 895.51 | | | | 695216 | | 1965906 | |
| | 0307 | Waterproofing lateral coating | Barrace | | 299.63 | 2.87 | 4681 72 | 4485 | - | 147104 | | 3.59 |
| | | bitumen in 2 layers on the | | | | | | | | | | |
| | | leveled surface of rubble | | | | | 4.40=00= | | | | | |
| 10 | 2105- | Hot-rolled reinforcing steel of a | T | 68.3 | 210429.00 | | 14372301 | | 14372301 | - | 15522085 | |
| • | • | | | | • | | | | | • | <u> </u> | |

| | 0301- 3202 | periodic profile of class A-III (A400) with a diameter of 14 to | | | - | - | | - | - | 1149784 | | - |
|-------|----------------|---|-------------------|--------|-----------|-----------------|-------------------|---------|----------|----------|----------|--------------|
| | | 32 mm ST RK 2591-2014 | | | 1 9 | 3 4 | | | | | | |
| 11 | 1137- | | м2 | 444.0 | 3648.10 | 249.90 | 1619758 | 110957 | 812751 | 663114 | 2465502 | 653.57 |
| | 0104- 0204 | Stationary wooden stationary simple massive blocks. | sealed surface | | 1567.68 | 73.53 | 696050 | 32647 | - | 182630 | | 21.19 |
| | | Installation and disassembly | Surracc | | | | | | | | | |
| | | when 10-25 t concrete tower | | | | | | | | | | |
| 12 | 1106- 0101- | Reinforced concrete foundation slabs flat. Device | м3 | 426.9 | 21508.74 | 1906.13 | 9182081 | 813726 | 7450037 | 998472 | 10994997 | 878.77 |
| | 0115 | Sidos flat. Device | | | 2151.13 | 419.08 | 918 318 | 178904 | - | 814444 | | 141.29 |
| 13 | 1106- | | м3 | 65.025 | 15994.07 | 124 1.59 | 1040014 | 80734 | 871049 | 95686 | 1226556 | 100.95 |
| | 0101- 0101 | Concrete preparation. Device | | | 1356.88 | 260.20 | 88231 | 16919 | - | 90856 | | 13.56 |
| | 0101 | | | _ | | | 27613385 | 1041260 | 24401354 | 2196843 | 32195046 | 2014.23 |
| | | Total section number 2 | | | | | 2170771 | 232955 | - | 2384818 | 02100010 | 179.63 |
| | | Section No. 3 Frame | | | Į I | | | | I | | | |
| 14 | 1106- | | м3 | 293.76 | 66542.93 | 31647.41 | 19 547 651 | 9296744 | 5434479 | 6172352 | 27777603 | 4199.15 |
| | 0501- 0201 | Columns of civil buildings in | MS | 200.10 | 16395.79 | 6693.82 | 4816428 | 1966376 | - | 2057600 | 2 | 1571.42 |
| | 0201 | metal formwork. Device | | | | 0000.02 | 10.10.120 | | | 200.000 | | |
| 15 | 2105- | | Т | 41.1 | 210429.00 | - | 8648632 | | 8648632 | - | 9340523 | |
| | 0301- 3202 | Hot-rolled reinforcing steel of | | | - | | | - | - | 691891 | | - |
| | | | | | | | | | | | | |
| | | periodic profile of class A-III | | | | | | | | | | |
| 16 | 1137- 0104- | | м2 sealed surface | 2937.6 | 7644.45 | 226.67 | 22456330 | | 14888420 | 6377277 | 31140296 | 6384.87 |
| | 0601 | Metal mesh formwork. Installation and disassembly | Surrece | | 2349.55 | 36.0 7 | 6902 048 | 105949 | - | 2306689 | | 70.61 |
| | | when 10-25 t concrete tower | | | | | | | | | | |
| CME | TA PK 201 | cranes are supplied | | | | - 4 - | | | | | 16 5 | c 02-001-001 |
| CIVIE | | • | | | 1 | - 4 - | | | | | | |
| 1 | 2 | 3 | 4 | 5 | 6 | | 8 | 9 | 10 | 11 | 12 | 13 |
| | | Total for section No. 3 | | | | | 50652613 | 9962606 | 28971531 | 12549629 | 68258422 | 10584.02 |
| | | | | | | | 11718476 | 2072325 | - | 5056180 | | 1642.03 |
| | | Section No. 4 Overlap | | | | | | | | | | |
| • | | | | | | | | | | | | · |

| 17 | 1106- | Bezel-less overlappings up to | м3 | 2250.0 | 36752.46 | 2067.30 | 82693031 | 4651417 | 55830773 | 21139660 | 112139306 | 20855.25 |
|-----|----------------|---|------------------|----------|------------|----------------|------------------|---------|-----------|----------|------------|--------------|
| | 0801- 0101 | 200 mm thick. The device at a height of from the reference area | | | 9871.48 | 453.14 | 22210841 | 1019555 | - | 8306615 | - | 806.52 |
| 18 | 2107- | | м2 | 11250.0 | 15707.00 | J 4 | 176703750 | | 176703750 | - | 190840050 | |
| | 0510- 1003 | The formwork is collapsible and permutable panel board, ShchD | | | | - | | - | _ | 14136300 | - | - |
| | | brand 1,5x0,4, size | | | | | | | | | | |
| | | 1500x400x417 mm GOST | | 4 | | | | | | | | |
| 19 | 2105- | 23477-79 Hot-rolled reinforcing steel of a | T | 270.0 | 210429.00 | | 5681 5830 | | 56815830 | _ | 61361096 | |
| | 0301- | periodic profile of class A-III | | | 4 | | | _ | | 4545266 | - | |
| | 3202 | (A400) with a diameter of 14 to 32 mm ST RK 2591-2014 | | | <i>I</i> 4 | | | | | 4343200 | | |
| | | 32 mm 31 KK 23/1-2014 | | | | | | | | | | |
| | | Total section number 4 | | | | | 316212611 | 4651417 | 289350353 | 21139660 | 364340452 | 20855.25 |
| | | Total section number 4 | | | | | 2 2210841 | 1019555 | 209330333 | 26988181 | 304340432 | 806.52 |
| | | | | | | | 22210041 | 1019555 | - | 20900101 | | 000.52 |
| | | Section No. 5 Walls | | T | | | | | | | | |
| 20 | 1108- 0701- | | м2 | 5100.0 | 736.39 | 2.12 | 3755608 | 10806 | 1033940 | 2525867 | 6783993 | 2545.41 |
| | 0101 | Outdoor inventory woods up to 16 m high tubular for masonry | вертикальн ой | | 531.54 | 1.00 | 2710862 | 5124 | - | 502518 | - | 4.11 |
| | | and cladding. Installation and | проекции | | | | | | | | | |
| | | disassembly | | | | | , T | | | | | |
| 21 | 1108- | Walls made of light concrete | м3 кладки | 3060.0 | 9050.69 | 3005.13 | 27695108 | 9195710 | 4557824 | 14762752 | 45854489 | 13090.68 |
| | 0301- 0101 | stones. Masonry without cladding with a floor height of | | | 4556.07 | 631.49 | 13941574 | 1932353 | - | 3396629 | - | 1548.36 |
| | | up to 4 m | | | | | | | | | | |
| | ļ | Total section number 5 | | | | | 31450716 | 9206516 | 5591764 | 17288619 | 52638482 | 15636.09 |
| | | | | | | | 16652436 | 1937477 | - | 3899147 | - | 1552.47 |
| | | Section No. 6 Roofing | | | | | | | | ļ | | |
| 22 | 4440 | Section 10. 0 Rooming | | L 605.0 | 1 2220.04 | 450 50 | 0007444 | 0.4440 | 4704700 | 000070 | 0.40000001 | 400.00 |
| 22 | 1112- 0101- | | м2 кровли | 625.0 | 3339.91 | 150. 58 | 2087444 | | 1764792 | 220878 | 2492988 | 189.03 |
| | 0201 | Four-layer flat roofs from rolled roofing materials on | | | 365.66 | 18.47 | 228539 | 11546 | - | 184666 | | 8.48 |
| | | bitumen mastic with a | | | | _ | | | | | | |
| | | protective layer of gravel on | | | | | | | | | | |
| | | antiseptic bitumen mastic. | | | | | | | | | | |
| CME | TA PK 201 | <u>Пеуісе</u> 8 Триал | | | | - 5 - | | | | | 16_л | c 02-001-001 |
| 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 |
| | | Total for section No. 6 | | | | | 2087444 | 94113 | 1764792 | 220878 | 2492988 | 189.03 |
| I | l | I | l | 1 | | | l | l | Ţ | ļ | ļ | Į |

| | | | | | | | 228539 | 11546 | - | 184666 | | 8.48 |
|-----|---------------|--|----------------------|---------|----------|-------|-------------------|----------|------------|-------------------|-----------|----------|
| | | Section No. 7 Exterior Finishing | | | 1 0 | 2 4 | ı | | I | I | l | |
| 23 | 1115- | | м2 | 4332.0 | 9491.06 | 52.43 | 41115257 | 227131 | 1141014 | 31835138 | 78786427 | 31848.65 |
| | 0109- 0101 | Facades ventilated on a metal frame. Fiber cement cladding | cladding surfaces | | 9175.23 | 10.81 | 39747112 | 46810 | - | 5836032 | - | 30.89 |
| | | device with cradles | surraces | | | | | | | | | |
| 24 | 2103- | | м2 | 4332.0 | - | - | - | | - | - | - | |
| | 0499- 9903 | Straight stone facing | | | | | | | | | | |
| ŀ | | T 1 1 7 | | | 4 | | 41115257 | 227131 | 1141014 | 31835138 | 78786427 | 31848.65 |
| | | Total section number 7 | | | | | 39747112 | 46810 | - | 5836032 | _ | 30.89 |
| | | | | | | | | | ļ | ļ | Į | |
| 25 | 1115- | Section No. 8 Interior Finishing | м2 | 15300.0 | 1203.88 | 80.31 | 18 419354 | 1228705 | 4072697 | 11276902 | 32071956 | 11436.75 |
| 23 | 0203- 0201 | Walls inside buildings. | plastered | 10000.0 | 857.38 | | 13117952 | 978176 | 4072037 | 2375700 | 3207 1330 | 936.05 |
| | 0201 | Plastering with cement-lime or cement mortar on stone and | surface | | 037.30 | 00.00 | 10117332 | 370170 | | 2373700 | | 330.03 |
| ŀ | | concrete is simple | | | | , | 18419354 | 1228705 | 4072697 | 11276902 | 32071956 | 11436.75 |
| | | Total section number 8 | | | | | 13117952 | 978176 | - | 2375700 | _ | 936.05 |
| | | Total estimate | | | | | 492544629 | 27142336 | 357376020 | 98573477 | 638407553 | 94257.54 |
| | | | Tenge | | | | 638407553 | E15U113 | | 470 <u>0</u> 0447 | | 5277 OO |
| | | Total estimate: including: | Tenge | | | | | | | | | |
| | | | Tenge | | | | 108026273 | | | | | |
| | | - salary of construction workers | Tenge | | | | 27142336 | | | | | |
| | | - the cost of operating the | renge | | | | 27 142000 | | | | | |
| | | machines | Tenge | | | | 6480143 | | | | | |
| | | - including the salary of drivers | renge | | | | 0.001.10 | | | | | |
| | | - materials, products and designs | Tenge | | | | 357 376020 | | | | | |
| | | inaterials, products and designs | renge | | | | | | | | | |
| | | | Tenge | | | | 985734 77 | | | | | |
| | | - overhead | 101180 | | | | | | | | | |
| CME | TA PK 2018 | · | | - 6 - | | | | | 02-001-001 | | | |
| 1 | 2 | 3 4 | 5 | 6 7 | 8 | 9 | 10 11 | 12 | 13 | | | |
| | - es | timated profit Tenge | | | 47289447 | | | | | | | |
| 1 1 | 1 | 1 1 | I | I | | | I | I | 1 I | | | |

| Compiled | Position ,sign ,surname) | ature (initials | 3 4 |
|----------|-----------------------------|------------------|-----|
| Checked | | | |
| | position, sign | ature (initials, | |

CMETA PK 2018 Триал 16_ccp

Appendix 4 to the normative document for the determination of the estimated cost of construction in the Republic of Kazakhstan


| | Kargar Construction group of compaany TM | farm 2 |
|--|--|----------------|
| Customer | Tangar Constitution group of Company | |
| Approved / Approved | (name of company) | |
| Estimated construction cost in the amount of | | thousand tenge |
| including: value added tax | 76608.906 | thousand tenge |
| | | |
| | (reference to the document on approval / approval) | |
| "20г. | Estimated cost of construction | |
| | Multi-storey Hpstel | |
| | (name of construction site) | |


Compiled at current prices as of 2020. No. of estimates and calculations other documents


| No | No. of estimates and calculations other | | Es | stimated cost, thousand te | nge | |
|-----|---|--|-----------------------------|-----------------------------------|------------|-----------------------|
| п/п | | Name of chapters objects, work and costs | construction assembly works | equipment furniture and inventory | other cost | Total, thousand tenge |
| 1 | 2 | 3 | 4 | 5 | 6 | 7 |


| | | Chapter 2. The main objects of construction | | |
|---|------------------------------------|---|-----------|------------|
| 1 | 02-001 | Многоэтажное общежитие 638407.553 | | 638407.553 |
| | | Total Chapter 2 638407.553 | | 638407.553 |
| | | Total chapters 1 - 7 638407.553 | | 638407.553 |
| | | Total chapters 1 - 9 638407.553 | | 638407.553 |
| | | Total estimated cost 638407.553 | | 638407.553 |
| 2 | Code of the republic of Kazakhstan | Value Added Tax (VAT) - 12% | 76608.906 | 76608.906 |
| | 99-IV Artil268 | Total estimated 638407.553 | 76608.906 | 715016.459 |


| Project Manager | |
|-----------------|--------------------------------------|
| | signature (initials, surname) |
| | |
| | signature (initials, surname) |
| | |
| | |
| | (name) signature (initials, surname) |

















Schedule Labor costs Months Construction of the processor Names August May Julay September June octobar 6 7 8 9 2 4 8 10 14 6 18 22 24 28 20 11 15 17 20 23 28 28 28 28 3 3 6 11 15 17 20 23 28 28 28 3 1 3 6 8 12 14 16 20 22 28 28 28 3 5 8 11 4 17 10 23 28 28 27 3 4 3 5 15.67 Earthworks nstallation of cast-in-place foundation works oundry works 35.67 184.33 2 T / b with ingot hardness core 496 2 1 мз 1050 1 22 22 23 439 2 works.Normal installation Cast ladder 26.63 101 works Walls and partitions of wall works 156 650 134 Wall plastering 6750 Cement mortar and 1 м2 205 3250 ceramic tile 200 Ventilation and heating Water supply and sewerage 200 140 Wiring 60 Gas supply works 10 Workforce schedule The maximum number of employees is N max = 52 people Mid- workers an average of N = Q / t = 4775/120 = 40people Coefficient of uniform flow of labor K= Nmax/Nopr=52/40=1.3<1.5 Technical and economic indicators Construction time - 180 days The total labor intensity in construction is 3245 people The coefficient of uniform movement of labor K = 1.3<1.5 KAZNITU-5B072900-Civil Engineering-29-05-2020-DP "Multi-story hostel" in Taraz Chan, Num par. List doc Sigh date Dean of kaf A.Akmalayuli list lists The Technological Part of the N.controller Kozyukova N. 8 construction CW Supervisor Kozyukova N.\ Consultant Коzyuкоva V. Стеаted Babur Kargar Consultant Kozyukova N.V Department of construction Schedule and construction materials Workforce schedule

Протокол анализа Отчета подобия Научным руководителем

| Заявляю, что я ознакомился(-ась) с Полным отчетом подобия, который был с Системой выявления и предотвращения плагиата в отношении работы: | генерирован |
|---|---|
| Автор: Каргар Бабур | |
| Название: Multi-storey hostel in Taraz | |
| Координатор:Надежда Козюкова | |
| | |
| Коэффициент подобия 1:3,9 | |
| 1934 | |
| Коэффициент подобия 2:0,6 | |
| | |
| Замена букв:28 | |
| Интервалы:0 | |
| Микропробелы:0 | |
| Белые знаки: 0 | |
| | |
| После анализа Отчета подобия констатирую следующее: | |
| □ обнаруженные в работе заимствования являются добросовестными и н признаками плагиата. В связи с чем, признаю работу самостоятельной и до защите; | е обладают эпускаю ее к |
| □ обнаруженные в работе заимствования не обладают признаками плагиата, но их количество вызывает сомнения в отношении ценности работы по отсутствием самостоятельности ее автора. В связи с чем, работа должна отредактирована с целью ограничения заимствований; | чрезмерное существу и быть вновь |
| □ обнаруженные в работе заимствования являются недобросовестными признаками плагиата, или в ней содержатся преднамеренные искаже указывающие на попытки сокрытия недобросовестных заимствований. В св допускаю работу к защите. | и обладают эния текста, язи с чем, не |
| Обоснование: | |
| Обнаруженные в работе заимствования являются добросовестными, и не обладают признака В связи с чем, признаю работу самлетоятельной и допускаю ее к защите. | ми плагиата. |
| | |
| Дата Подпись Научного руководителя | ı |
| | |

Протокол анализа Отчета подобия

заведующего кафедрой / начальника структурного подразделения

Заведующий кафедрой / начальник структурного подразделения заявляет, что ознакомился(-ась) с Полным отчетом подобия, который был сгенерирован Системой выявления и предотвращения плагиата в отношении работы:

| Anmon, Monroe Fo | Serve . | | | | | | |
|---|--|--|--|--|--|--|--|
| Автор: Каргар Бабур | | | | | | | |
| Название: Multi- | Hазвание: Multi-storey hostel in Taraz | | | | | | |
| Координатор: На | адежда Козюкова | | | | | | |
| | 1001 | | | | | | |
| Коэффициент по | одобия 1:3,9 | | | | | | |
| Коэффициент по | одобия 2:0,6 | | | | | | |
| Замена букв:28 | | | | | | | |
| Интервалы:0 | | | | | | | |
| Микропробелы: | 0 | | | | | | |
| Белые знаки:0 | | | | | | | |
| | | | | | | | |
| | гчета подобия заведующий кафедрой / начальник структурного констатирует следующее: | | | | | | |
| плагиата. В связи □ обнаруженные количество вызын самостоятельност ограничения заим □ обнаруженные плагиата, или в не | в работе заимствования являются добросовестными и не обладают признаками с чем, работа признается самостоятельной и допускается к защите; в работе заимствования не обладают признаками плагиата, но их чрезмерное зает сомнения в отношении ценности работы по существу и отсутствием и ее автора. В связи с чем, работа должна быть вновь отредактирована с целью иствований; в работе заимствования являются недобросовестными и обладают признаками ей содержатся преднамеренные искажения текста, указывающие на попытки осовестных заимствований. В связи с чем, работа не допускается к защите. | | | | | | |
| Обоснование: | | | | | | | |
| | в работе заимс твования являю тся добросовест ными | | | | | | |
| | тризнаками плагиата. | | | | | | |
| -В-связи-с чем; р | абота признается самостоятельной и допускается к защите; | | | | | | |
| | | | | | | | |
| | Specie | | | | | | |
| Лата | Подпись заведующего кафедрой / | | | | | | |

начальника структурного подразделения

| Окончательное решение в | отношении допуска к защите, включая обоснование: |
|-------------------------|--|
| Работа признается само | стоятельной и допускается к защите. |
| Обнаруженные в работ | е заимствования являются добросовестными |
| | ами плагиата |
| | |
| | |
| Дата | Подпись заведующего кафедрой / |
| | начальника структурного подразделения |
| | 1934 |



МИНИСТЕРСТВО ОБРАЗОВАНИЯ И НАУКИ РЕСПУБЛИКИ КАЗАХСТАН СӘТБАЕВ УНИВЕРСИТЕТІ

RESPONSE

OF THE SUPERVISOR

for the graduation project

Kargar Babur 5B072900-Civil Engineering

Topic: "Multi-storey hostel in Taraz"

Graduation project of Kargar Babur made in accordance with the requirements and includes all the necessary sections of the diploma project. In the Architectural part, facades, sections, floor plans and connection nodes of structures are presented. The thermotechnical calculation of the wall fencing was made.

In the constructive section, the calculation of the floor slab, frames on the LIRA CAD program is performed. In the technological part, technological maps for earthworks and stone works have been developed.

The economic part of the project is calculated according to the program of SMETA of the RK. All drawings are made in Autocad.

In general, the graduation project was performed at a good level, the student Kargar Babur showed good knowledge both during training and during the implementation of the project. The work deserves a good grade.

Supervisor

Master of technical science, lecturer

____ Kozyukova N.V.

«25 » 05 2020 г.